

令和 8 年度

市道第4081号線ほか舗装修繕工事
本庄市牧西 地内

数 量 計 算 書

積算数量一覧表

工事区分 (LEVEL1)	工 種 (LEVEL2)	種 別 (LEVEL3)	細 別 (LEVEL4)	規 格 (LEVEL5)	単位	数値	設計数量	積算数量		摘 要
整備工事										
	構造物 撤去工				式		1	1		
		舗装版破砕	t ≤ 15cm		m2	10	2164.5	2160.0		
		再生密粒度 殻運搬処理	アスコン	t=5cm	m3	1	108.2	108.0		
		舗装版切断	t=15cm以下		m	1	21.0	21.0		
		舗装切断 濁水処理			m ³		0.027	0.03		
	舗装工				式		1	1		
		表層	再生密粒度 アスコン	t=5cm	m2	10	2164.5	2160.0		
		不陸整正	補足材有		m2	10	2164.5	2160.0		
	区画線工				式		1	1		
		区画線設置	実線 白15		m	10	652.0	650.0		
		区画線設置	破線 白30		m	1	7.0	7.0		
		区画線設置	実線 白45		m	1	3.0	3.0		
		区画線設置	実線 橙15		m	10	652.0	650.0		
		区画線設置	文字記号 白15換算		m	1	50.5	51.0		
	仮設工	交通誘導 警備員	交通誘導 警備員B		人日	1				

積 算 数 量 一 覧 表

工事区分 (LEVEL1)	工 種 (LEVEL2)	種 別 (LEVEL3)	細 別 (LEVEL4)	規 格 (LEVEL5)	単位	数値	設計数量	積算数量		摘 要
整備工事										
	構造物 撤去工				式		1	1		
		舗装版破碎	t ≤ 15cm		m2	1	698.0	698.0		
		再生密粒度 殻運搬処理	アスコン	t=5cm	m3	1	34.9	35.0		
		舗装版切断	t=15cm以下		m	1	43.0	43.0		
		舗装切断 濁水処理			m ³		0.056	0.06		
	舗装工				式		1	1		
		表層	再生密粒度 アスコン	t=5cm	m2	1	698.0	698.0		
		不陸整正	補足材有		m2	1	698.0	698.0		
	区画線工				式		1	1		
		区画線設置	実線 白15		m	10	168.0	170.0		
		区画線設置	破線 白15		m	1	15.0	15.0		
		区画線設置	実線 白45		m	10	103.5	100.0		
	仮設工	交通誘導 警備員	交通誘導 警備員B		人日	1				

構造物撤去工調書

(第1工区)

数 量 調 書

工 種 (レベル2)	構造物撤去工	種 別 (レベル3)	構造物取壊し工・運搬処理工
1. 舗装版取壊し			
1) 破砕面積 t=15cm以下 A = = 2,164.5 m2			
2) 破砕量 t=5cm V = = 108.2 m3			
2. ガラ運搬処理 (アスコン廃材)			
t=5cm V = = 108.2 m3			
3. 舗装切断(t=15cm以下) L = = 21.0 m			
4. 舗装切断濁水処理 V = = 0.027 m3			

[illegible]

舗 装 工 調 書

(第 1 工区)

数 量 調 書

工 種 (レベル2)	舗装工	種 別 (レベル3)	アスファルト舗装工
---------------	-----	---------------	-----------

[illegible]

[illegible]

舗装平積				第1工区	
舗 装 計 算 書					
測 点	距 離	舗 装 幅	平 舗 装 幅	平 積	備 考
No. 0		6.500			全面
No. 1	20.000	6.500	6.500	130.00	全面
No. 2	20.000	6.500	6.500	130.00	全面
No. 3	20.000	6.500	6.500	130.00	全面
No. 4	20.000	6.500	6.500	130.00	全面
No. 5	20.000	6.500	6.500	130.00	全面
No. 6	20.000	6.500	6.500	130.00	全面
No. 7	20.000	6.500	6.500	130.00	全面
No. 8	20.000	6.500	6.500	130.00	全面
No. 9	20.000	6.500	6.500	130.00	全面
No. 10	20.000	6.500	6.500	130.00	全面
No. 11	20.000	6.500	6.500	130.00	全面
No. 12	20.000	6.500	6.500	130.00	全面
No. 13	20.000	6.500	6.500	130.00	全面
No. 14	20.000	6.500	6.500	130.00	全面
No. 15	20.000	6.500	6.500	130.00	全面
No. 16	13.000	6.500	6.500	84.50	全面
No. 16 +13.0		6.500			全面
小 計	333.000			2164.50	

区 画 線 工 調 書

(第 1 工区)

数 量 調 書

工 種 (レベル2)	区画線工	種 別 (レベル3)	区画線設置工
1. 区画線設置工			
1) 実線 白15 L= 652.0 m			
2) 破線 白30 L= 7.0 m			
3) 実線 白45 L= 3.0 m			
4) 実線 橙15 L= 652.0 m			
5) 文字記号 白15換算 L= 50.5 m			

第 1 工区									
区画線設置工集計表									
区画線設置 計算書より									
実線	白15	L=	326.0	×	2.0	=	652.0	m	
破線	白30	L=	0.5	×	7.0	×	2.0	=	7.0 m
実線	白45	L=	3.0			=	3.0	m	
実線	橙15	L=	326.0	×	2.0	=	652.0	m	
文字記号	白15換算	L=	8.8	+	12.6	+	8.8		
		+	11.0	+	9.3	=	50.5	m	

構造物撤去工調書

(第2工区)

数 量 調 書

工 種 (レベル2)	種 別 (レベル3)	構造物撤去工	構造物取壊し工・運搬処理工
1. 舗装版取壊し			
1) 破砕面積 t=15cm以下 A = 698.0 m2			
2) 破砕量 t=5cm V = 34.9 m3			
2. ガラ運搬処理 (アスコン廃材)			
t=5cm V = 34.9 m3			
3. 舗装切断(t=15cm以下) L = 43.0 m			
4. 舗装切断濁水処理 V = 0.056 m3			

第 2 工区									
取壊工集計表									
舗装版破碎 (As, 15cm以下)					計算書より				
t=5cm		A =		698. 0		=		698. 0 m2	
計								698. 0 m2	
		V =		698. 0		×		0. 05	
						=		34. 9 m3	
カッター切断 (As)					図面より				
t=15cm以下									
		L =		19. 0		+		17. 0	
						+		7. 0	
						=		43. 0 m	
					切断延長 V=0. 13m3:濁水处理m3/100m				
舗装切断濁水处理		V =		43. 0		×		0. 0013	
						=		0. 056 m3	

舗 装 工 調 書

(第 2 工区)

数 量 調 書

工 種 (レベル2)	舗装工	種 別 (レベル3)	アスファルト舗装工
---------------	-----	---------------	-----------

[illegible]

[illegible]

[illegible]

区 画 線 工 調 書

(第 2 工区)

数 量 調 書

工 種 (レベル2)	区画線工	種 別 (レベル3)	区画線設置工
1. 区画線設置工			
1) 実線 白15 L= = 168.0 m			
2) 破線 白15 L= = 15.0 m			
3) 実線 白45 L= = 103.5 m			

区画線設置工集計表

区画線設置		計算書より							
実線	白15	L=	58.0	+	80.0	+	30.0	=	168.0 m
破線	白15	L=	5.0	×	3.0			=	15.0 m
実線	白45	L=	6.0	×	6.0			=	36.0 m
		L=	8.5	×	7.0	+	5.0	=	64.5 m
		L=	3.0					=	3.0 m
	計	L=	36.0	+	64.5	+	3.0	=	103.5 m