

数量総括書

一般県道 大多喜里見線 市原市 月出

種 別	規格	単位	算 式	合計数量	設計数量
道路修繕					
舗装工					
路面切削工					
路面切削	t=4cm切削	m2	$A=1511.7 = 1511.7$	1511.7	1510
殻運搬	As殻	m3	$A=1511.7 \times 0.04 = 60.4$	60.4	60
殻処分	As殻	m3	$A=1511.7 \times 0.04 = 60.4$	60.4	60
切削オーバーレイ工					
切削オーバーレイ 再生粗粒度As(20)溶融スラグ入	t=6cm切削 t=5cm舗設	m2	$A=1511.7 = 1511.7$	1511.7	1510
殻運搬	路盤スラグ廃材	m3	$A=1511.7 \times 0.06 = 90.7$	90.7	91
殻処分	路盤スラグ廃材	m3	$A=1511.7 \times 0.06 = 90.7$	90.7	91
オーバーレイ工					
表層 再生密粒度As(20)溶融スラグ入	t=5cm	m2	$A=1511.7 = 1511.7$	1511.7	1510
区画線工					
区画線工					
溶融式区画線	実線15cm 白	m	$L=540 = 540.0$	540.0	540
仮設工					
交通管理工					
交通誘導員	B 夜間	人日	$= 20.0$	20.0	20
交通誘導員	B 昼間	人日	$= 2.0$	2.0	2
直接工事費					
共通仮設					
共通仮設費					
運搬費					
建設機械運搬費		台	$= 2.0$	2.0	2

数量計算書

表層・基層

測点	測点間距離	幅員	平均幅員	面 積	測点	測点間距離	幅員	平均幅員	面 積
No.0	20.0				No.20	20.0	5.57		
No.1					No.21		5.77	5.67	113.4
No.1	20.0				No.21	6.8	5.77		
No.2					No.21+6.8		6.21	5.99	40.7
No.2	20.0				No.21+6.8	13.2	6.21		
No.3					No.22		5.27	5.74	75.8
No.3	20.0								
No.4									
No.4	20.0								
No.5									
No.5	20.0								
No.6									
No.6	20.0								
No.7									
No.7	20.0								
No.8									
No.8	10.0								
No.8+10									
No.8+10	10.0	6.00							
No.9		5.35	5.68	56.8					
No.9	20.0	5.35							
No.10		5.40	5.38	107.6					
No.10	20.0	5.40							
No.11		4.90	5.15	103.0					
No.11	20.0	4.90							
No.12		5.45	5.18	103.6					
No.12	20.0	5.45							
No.13		6.76	6.11	122.2					
No.13	20.0	6.76							
No.14		5.40	6.08	121.6					
No.14	20.0	5.40							
No.15		6.22	5.81	116.2					
No.15	20.0	6.22							
No.16		5.60	5.91	118.2					
No.16	20.0	5.60							
No.17		5.05	5.33	106.6					
No.17	20.0	5.05							
No.18		5.55	5.30	106.0					
No.18	20.0	5.55							
No.19		5.57	5.56	111.2					
No.19	20.0	5.57							
No.20		5.30	5.44	108.8					
No.20	20.0	5.30							
小計	230.0			1281.8	小計	40.0			229.9
					合計	270.0			1511.7

区画線(表層)

工種	規格	計算				数量
溶融式区画線 実線15cm	15cm実線 白 外側線	270.0	*	2	=	540.0 m
		No.8+10～No.22		両側		