

北坂戸さかろんパーク整備工事

代価数量計算書


単位数量計算書

(構造物等撤去工)

種 別 施設撤去工
細 別 フェンスA 撤去

(10m) 当り

略図



種 別	規 格	計 算 式	単位	数 量
<処分>				
金属くず		$((0.0508 \times 0.0016 \times 1.40) \times 5 + (0.0508 + 0.0508) \times 0.0016 \times 10) \times 7850 / 1 =$	t	0.017
殻積込・運搬・処分	Co(無筋)	$(0.5 \times 0.2 + 0.18 \times 0.6) \times 10 =$	m3	2.08
床掘		$0.5 \times 0.8 \times 10 =$	m3	4.00
埋戻し		$(0.5 \times 0.18 + 0.18 \times 0.62) \times 10 =$	m3	2.02


種 別	施設撤去工			
細 別	フェンスB 撤去		(10m) 当り	
略図				
種 別	規 格	計 算 式	単位	数 量
<処分>				
金属くず		$((0.0508 \times 0.0016 \times 3.0) \times 5 + (0.0508 + 0.0508) \times 0.0016 \times 10 \times 2) \times 7850 / = 0.035$	t	0.035
殻積込・運搬・処分	Co(無筋)	$0.18 \times 0.18 \times 0.45 \times 10 / 2 = 0.073$	m3	0.07
床掘		$0.18 \times 0.18 \times 0.45 \times 10 / 2 = 0.073$	m3	0.07
埋戻し		$0.18 \times 0.18 \times 0.45 \times 10 / 2 = 0.073$	m3	0.07

(給水設備工)

種 別 弁柵工
細 別 量水器ボックス

(10基) 当り

略図




種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$1.015 \times 0.815 \times 10 = 8.272$	m2	8.27
型枠	小型	$((0.915 + 0.715) \times 2 \times 0.47 + (0.715 \times 0.515) \times 2 \times 0.37) \times 10 = 18.047$	m2	18.05
コンクリート	18-8-25	$(0.915 \times 0.715 \times 0.47 - 0.715 \times 0.515 \times 0.37) \times 10 = 1.712$	m3	1.71
量水器柵ふた	鋳鉄製 MB-2	$10 = 10.000$	個	10.00
止水栓	φ40	$10 = 10.000$	個	10.00
メーター交換	口径40mm	$10 = 10.000$	箇所	10.00
		土工事は管路土工に含む。		

種 別 弁柵工
細 別 止水栓 GV20A

(10基) 当り

略図




種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=150	$(0.3/2)^2 \times 3.14 \times 10$	m2	0.71
再生クラッシャーラン基礎	RC-40 t=100	$((0.4/2)^2 - (0.216/2)^2) \times 3.14 \times 10$	m2	0.89
型枠	小型	$0.3 \times 0.10 \times 4 \times 10$	m2	1.20
コンクリート	18-8-25	$(0.3 \times 0.3 - (0.216/2)^2) \times 3.14 \times 0.10 \times 10$	m3	0.05
硬質塩化ビニル管	VU φ 200	0.52×10	m	5.20
止水栓蓋	PVC製 φ 200用B1	10	個	10.00
止水栓	GV20A	10	個	10.00
		土工事は管路土工に含む。		

種 別 弁柵工
細 別 散水栓

(10基) 当り


略図



種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.4 \times 0.3 - 0.15 \times 0.15) \times 10 = 0.975$	m2	0.98
型枠		$0.1 \times 0.15 \times 4 \times 10 = 0.600$	m2	0.60
コンクリート	18-8-25	$0.15 \times 0.15 \times 0.1 \times 10 = 0.023$	m3	0.02
散水栓ボックス	B3A	10 = 10.000	個	10.00
キー付散水栓	13A	10 = 10.000	個	10.00
		土工事は管路土工に含む。		

(10m) 当り

略図



標準断面図


管種・径	d
HIVP-20	26
HIVP-25	32
HIVP-40	48

種 別	規 格	計 算 式	単位	数 量
給水管	HIVP-25A	10 = 10.000	m	10.00
埋設表示シート	W=150ダブル	10 = 10.000	m	10.00
		土工事は管路土工に含む。		

種 別 給水路設工
細 別 埋設表示鋏

(10個) 当り

略図







種 別	規 格	計 算 式	単 位	数 量
埋設表示鋏	ポロン製	10 = 10.000	個	10.00
		土工事は管路土工に含む。		

種 別 貯留施設工
細 別 防火水槽

(1基) 当り


略図



種 別 貯留施設工
細 別 防火水槽

(1基) 当り

略図



主要部材数量表

部 材 名	寸 法	単 位	数 量	単 位 質 量	質 量	備 考
土留め壁(鋼矢板)	Ⅲ型	m	629.000	60.0kg/m	37.74t	
計					37.74t	


種 別	貯留施設工		(1基) 当り		
細 別	防火水槽				
種 別	規 格	計 算 式	単位	数 量	
再生クランチャーラン基礎	RC-40 t=150	$3.9 \times 6.94 = 27.066$	m ²	27.07	
型枠	鉄筋	$(3.9+6.94) \times 2 \times 0.15 + (1.5+1.7) \times 2 \times 0.583 + (1.2+1.4) \times 2 \times 0.583 = 10.015$	m ²	10.01	
コンクリート	21-8-25	$3.9 \times 6.94 \times 0.15 + (1.5 \times 1.7 - 1.2 \times 1.4) \times 0.583 = 4.567$	m ³	4.57	
鉄筋	D10	$(3.9/0.3+1) \times 6.84 + (6.94/0.3+1) \times 3.8 + (1.4+1.6)/0.3 \times 2 \times 0.583 = 199.127$	t	0.11	
モルタル	t20 1:3	$199.127 \times 0.56 / 1000 = 0.112$			
マンホール蓋	φ 600	$(3.606 \times 6.645 - 1.2 \times 1.4) \times 0.02 = 0.446$	m ²	0.45	
防火水槽	貯水量40m ³	$6940 \times 3900 \times 2500 = 1.000$	枚	1.00	
<土留め工>					
土留め壁	鋼矢板Ⅲ型	$60.0\text{kg/m} \times 629 = 629.000$	m	37.7	
		$(629 \times 60.0) / 1000 = 37.740$	kg	37.74	
床掘		$9.0 \times 5.0 \times 3.776 + 1.7 \times 1.5 \times 0.583 = 171.407$	m ³	171.41	
埋戻し		$171.407 - 69.600 = 101.806$	m ³	101.81	
残土処分		$1.7 \times 1.5 \times 0.583 + 3.9 \times 6.94 \times 0.3 + 3.606 \times 6.645 \times (2.456 + 0.02) + (0.92 / 2)^2 \times 3.14 \times 1.0 = 69.600$	m ³	69.60	

(雨水排水設備工)

種 別 排水施設工
細 別 集水桝1

(10基) 当り

略図




インターA=300

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン	RC-40 t=100	$0.96 \times 0.96 \times 10 = 9.216$	m2	9.22
コンクリート	18-8-25	$(0.86 \times 0.86 \times 0.1) \times 10 = 0.740$	m3	0.74
型枠		$(0.1 \times 0.86 \times 4) \times 10 = 3.440$	m2	3.44
T-25用PC製集水桝	□500×800 477kg/個	$10 = 10.000$	基	10.00
グレーチング蓋	□500×500 T-25	$10 = 10.000$	枚	10.00
床掘		$(0.96 \times 0.96 \times 0.1 + 1.16 \times 1.16 \times 0.675) \times 10 = 10.004$	m3	10.00
埋戻し		$10.00 - 4.98 = 5.020$	m3	5.02
残土処分		$(0.96 \times 0.96 \times 0.1 + 0.86 \times 0.86 \times 0.1 + 0.76 \times 0.76 \times 0.575) \times 10 = 4.982$	m3	4.98
基面整正		$0.86 \times 0.86 \times 10 = 7.396$	m2	7.40

種 別 排水施設工
細 別 集水桝2

(10基) 当り

略図




インターA=300

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン	RC-40 t=100	$0.96 \times 0.96 \times 10 = 9.216$	m2	9.22
コンクリート	18-8-25	$(0.86 \times 0.86 \times 0.1) \times 10 = 0.740$	m3	0.74
型枠		$(0.1 \times 0.86 \times 4) \times 10 = 3.440$	m2	3.44
T-25用PC製集水桝	□500×1000 568kg/個	10 = 10.000	基	10.00
グレーチング蓋	□500×500 T-25	10 = 10.000	枚	10.00
床掘		$(0.96 \times 0.96 \times 0.1 + 1.16 \times 1.16 \times 0.875) \times 10 = 12.696$	m3	12.70
埋戻し		$12.70 - 6.14 = 6.560$	m3	6.56
残土処分		$(0.96 \times 0.96 \times 0.1 + 0.86 \times 0.86 \times 0.1 + 0.76 \times 0.76 \times 0.775) \times 10 = 6.138$	m3	6.14
基面整正		$0.86 \times 0.86 \times 10 = 7.396$	m2	7.40

種 別 排水施設工
細 別 集水枳3

(10基) 当り

略図




インターA=300

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン	RC-40 t=100	$1.28 \times 1.28 \times 10 = 16.384$	m2	16.38
コンクリート	18-8-25	$(1.18 \times 1.18 \times 0.1) \times 10 = 1.392$	m3	1.39
型枠		$(0.1 \times 1.18 \times 4) \times 10 = 4.720$	m2	4.72
T-25用PC製集水枳	□500×1250 1353kg/個	$10 = 10.000$	基	10.00
グレーチング蓋	□500×500 T-25	$10 = 10.000$	枚	10.00
床掘		$((1.15/3) \times ((1.48)^2 + (1.48 \times 2.63) + (2.63)^2) + (1.28 \times 1.28 \times 0.1)) \times 10 = 51.471$	m3	51.47
埋戻し		$51.47 - 15.28 = 36.190$	m3	36.19
残土処分		$(1.28 \times 1.28 \times 0.1 + 1.18 \times 1.18 \times 0.1 + 1.08 \times 1.08 \times 1.05) \times 10 = 15.278$	m3	15.28
基面整正		$0.86 \times 0.86 \times 10 = 7.396$	m2	7.40

種 別 排水施設工
細 別 集水枳4

(10基) 当り

略図




植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン	RC-40 t=100	$0.96 \times 0.96 \times 10 = 9.216$	m2	9.22
PC製集水枳	□600×1400	10 = 10.000	基	10.00
グレーチング蓋	□600×600 T-2	10 = 10.000	枚	10.00
床掘		$((1.40/3) \times ((1.30)^2 + (1.30 \times 2.70) + (2.70)^2) + (0.96 \times 0.96 \times 0.1)) \times 10 = 59.208$	m3	59.21
埋戻し		$59.21 - 12.26 = 46.950$	m3	46.95
残土処分		$(0.96 \times 0.96 \times 0.1 + 0.90 \times 0.90 \times 1.40) \times 10 = 12.262$	m3	12.26
基面整正		$0.86 \times 0.86 \times 10 = 7.396$	m2	7.40

種 別 排水施設工
細 別 浸透枳(角)

(10基) 当り

略図



植栽=0

種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	$0.82 \times 0.82 \times 10 = 6.724$	m2	6.72
透水シート		$((0.82 \times 0.82 - 0.52 \times 0.52) + 0.82 \times 0.6 \times 4) \times 10 = 23.700$	m2	23.70
単粒度碎石	4号	$(0.82 \times 0.82 \times 0.6 - 0.52 \times 0.52 \times 0.4) \times 10 = 2.953$	m3	2.95
浸透底塊フィルター	400用	$10 = 10.000$	個	10.00
浸透枳リング底塊		$10 = 10.000$	個	10.00
浸透下部側塊	520 × H300	$10 = 20.000$	個	20.00
浸透上部側塊	520 × H570	$10 = 10.000$	個	10.00
グレーチング蓋	□460用 T-14	$10 = 10.000$	枚	10.00


[illegible]

[illegible]

種 別 排水施設工
細 別 浸透柵(丸)-2段

(10基) 当り

略図



植栽,ダスト,AsA,AsB,インターA=(0+140+240+200+240+190)/6=168

種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	$0.88 \times 0.88 \times 10 = 7.744$	m2	7.74
透水シート		$(0.88 \times 1.23 \times 4 + 0.88 \times 0.88 + (0.88 \times 0.88 - 0.56 \times 0.56)) \times 10 = 55.648$	m2	55.65
単粒度碎石	4号	$(0.88 \times 0.88 \times 1.23 - 0.56 \times 0.56 \times 1.08) \times 10 = 6.138$	m3	6.14
浸透用リング底塊	390 × 80	$10 = 10.000$	個	10.00
浸透側塊	500 × 500	$2 \times 10 = 20.000$	個	20.00
異型甲500		$10 = 10.000$	個	10.00
浸透柵縁塊	560 × 560 × 100	$10 = 10.000$	個	10.00
グレーチング	□430 × 430 T-2	$10 = 10.000$	個	10.00


[illegible]

[illegible]

種 別 排水施設工
細 別 流入枳1

(10基) 当り

略図




植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン	RC-40 t=100	$0.96 \times 0.96 \times 10 = 9.216$	m2	9.22
PC製集水枳	□600×1400	10 = 10.000	基	10.00
グレーチング蓋	□600×600 T-2	10 = 10.000	枚	10.00
床掘		$((1.40/3) \times ((1.30)^2 + (1.30 \times 2.70) + (2.70)^2) + (0.96 \times 0.96 \times 0.1)) \times 10 = 59.208$	m3	59.21
埋戻し		$59.21 - 12.26 = 46.950$	m3	46.95
残土処分		$(0.96 \times 0.96 \times 0.1 + 0.90 \times 0.90 \times 1.40) \times 10 = 12.262$	m3	12.26
基面整正		$0.86 \times 0.86 \times 10 = 7.396$	m2	7.40

種 別 排水施設工
細 別 流入桧2

(10基) 当り

略図



植栽=0


種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	$0.88 \times 0.88 \times 10 = 7.744$	m2	7.74
透水シート		$(0.88 \times 1.23 \times 4 + 0.88 \times 0.88 + (0.88 \times 0.88 - 0.56 \times 0.56)) \times 10 = 55.648$	m2	55.65
単粒度碎石	4号	$(0.88 \times 0.88 \times 1.23 - 0.56 \times 0.56 \times 1.08) \times 10 = 6.138$	m3	6.14
浸透用リング底塊	390 × 80	10	個	10.00
浸透側塊	500 × 500	2 × 10	個	20.00
異型甲500		10	個	10.00
浸透桧縁塊	560 × 560 × 100	10	個	10.00
グレーチング	□430 × 430 T-2	10	個	10.00

[illegible]

種 別 排水施設工
細 別 流出桧

(10基) 当り

略図




AsA=240

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン	RC-40 t=100	$0.96 \times 0.96 \times 10 = 9.216$	m2	9.22
コンクリート	18-8-25	$(0.86 \times 0.86 \times 0.1) \times 10 = 0.740$	m3	0.74
型枠		$(0.1 \times 0.86 \times 4) \times 10 = 3.440$	m2	3.44
T-25用PC製集水桧	□500×800 477kg/個	$10 = 10.000$	基	10.00
グレーチング蓋	□500×500 T-25	$10 = 10.000$	枚	10.00
床掘		$(0.96 \times 0.96 \times 0.1 + 1.16 \times 1.16 \times 0.935) \times 10 = 13.503$	m3	13.50
埋戻し		$13.50 - 6.48 = 7.020$	m3	7.02
残土処分		$(0.96 \times 0.96 \times 0.1 + 0.86 \times 0.86 \times 0.1 + 0.76 \times 0.76 \times 0.835) \times 10 = 6.484$	m3	6.48
基面整正		$(0.96 \times 0.96) \times 10 = 9.216$	m2	9.22

種 別 排水施設工
細 別 大型雨水浸透貯留槽 (1基) 当り

略図



AsA=240 ※土砂捕捉壁工 長繊維不織布(4mm) 6.72m²、管接続工 長繊維不織布(4mm) 3.00m²


種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC40 t=150	21.11*21.11 = 445.632	m ²	445.63
クッション用砂	t=20	21.11*21.11 = 445.632	m ²	445.63
底板透水シート	t=4.0以上	20.165*20.71 = 417.617	m ²	417.62
大型雨水浸透貯留槽	点検人孔含む	1 = 1.000	基	1.00
保護シート	t=4.0以上	20.165*20.71+(20.165+20.71)*1.04*2 = 502.637	m ²	502.64
長繊維不織布	4mm	6.72+3.0 = 9.720	m ²	9.72
床掘		(20.165*20.71+20.825*21.37)/2*1.3 = 560.721	m ³	560.72
埋戻し		560.72-542.90 = 17.820	m ³	17.82
残土処分		20.165*20.71*1.3 = 542.902	m ³	542.90
基面整正		21.11*21.11 = 445.632	m ²	445.63

(汚水排水整備工)

種 別 汚水樹工
細 別 汚水樹(L型)-歩

(10基) 当り

略図




種 別	規 格	計 算 式	単位	数 量
塩ビ製汚水樹	PO-L 150-200	10 = 10.000	個	10.00
	ポリプロピレン製			
汚水樹蓋	防水・防臭耐圧蓋VU-200	10 = 10.000	個	10.00
		土工事は管路土工に含む。		

種 別 汚水樹工
細 別 汚水樹(ドロップ)-車

(10基) 当り

略図




種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC40 t150	$((0.545/2)^2 \times 3.142 - (0.216/2)^2 \times 3.142) \times 10 = 1.967$	m2	1.97
塩ビ製ドロップ樹	DR 150-200	10 = 10.000	個	10.00
90° 大曲エルボ	φ 150	10 = 10.000	個	10.00
防護蓋	鋳鉄製VU-200	10 = 10.000	個	10.00
		土工事は管路土工に含む。		


種 別 汚水樹工
細 別 汚水樹(90°合流ドロップ)-車

(10基) 当り

略図



平面図




断面図

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC40 t150	$((0.545/2)^2 \times 3.142 - (0.216/2)^2 \times 3.142) \times 10 = 1.967$	m2	1.97
塩ビ製90°合流ドロップ樹	DRY 150-200	10 = 10.000	個	10.00
90°大曲エルボ	φ150	10 = 10.000	個	10.00
防護蓋	鋳鉄製VU-200	10 = 10.000	個	10.00
		土工事は管路土工に含む。		

(10m) 当り

汚水管 (V U管)
床掘深さ1.0m以上



管種・径	外径d	内径r	管厚t	W	h
VU-100	114	100	6.6	714	314
VU-150	165	155	5.1	765	365


[illegible]

(電気設備整備工)

種 別 照明設備工
細 別 ポール照明

(10基) 当り

略図



種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン	RC-40 t=100	$(0.5/2)^2 \times 3.14 \times 10 = 1.963$	m2	1.96
スパイラルダクト	φ 500	$1.10 \times 10 = 11.000$	m	11.00
コンクリート	18-8-25	$((0.5/2)^2 \times 1.1 - (0.1016/2)^2 \times 0.9) \times 3.14 \times 10 = 2.086$	m3	2.09
接地工	D種	$1.00 \times 10 = 10.000$	極	10.00
床掘り		$(0.5/2)^2 \times 3.14 \times 1.3 \times 10 = 2.551$	m2	2.55
埋戻し		$2.55 - 2.36 = 0.190$	m3	0.19
残土処分		$(0.5/2)^2 \times 3.14 \times 1.2 \times 10 = 2.355$	m2	2.36

(10基) 当り

Technical drawing of a vertical pipe assembly. The drawing shows a side view and a top view. The side view includes dimensions: 1200 (total height), 800 (height to the top of the pipe), 400 (height to the bottom of the pipe), 268 (height to the top of the pipe), 100 (height to the bottom of the pipe), 138 (height to the top of the pipe), and 100 (height to the bottom of the pipe). The top view shows a circular pipe with a diameter of $\phi 114.3$. The side view shows a pipe with a diameter of $\phi 114.3$ and a flange with a diameter of $\phi 100$. The flange has a thickness of 13.8. The pipe has a wall thickness of 10. The drawing includes labels: ① (pointing to the pipe), ② (pointing to the pipe), ③ (pointing to the pipe), ④ (pointing to the flange), ⑤ (pointing to the pipe), ⑥ (pointing to the pipe), ⑦ (pointing to the pipe), ⑧ (pointing to the pipe), ⑨ (pointing to the pipe), ⑩ (pointing to the pipe), ⑪ (pointing to the pipe), ⑫ (pointing to the pipe), ⑬ (pointing to the pipe), ⑭ (pointing to the pipe), ⑮ (pointing to the pipe), ⑯ (pointing to the pipe), ⑰ (pointing to the pipe), ⑱ (pointing to the pipe), ⑲ (pointing to the pipe), ⑳ (pointing to the pipe), ㉑ (pointing to the pipe), ㉒ (pointing to the pipe), ㉓ (pointing to the pipe), ㉔ (pointing to the pipe), ㉕ (pointing to the pipe), ㉖ (pointing to the pipe), ㉗ (pointing to the pipe), ㉘ (pointing to the pipe), ㉙ (pointing to the pipe), ㉚ (pointing to the pipe), ㉛ (pointing to the pipe), ㉜ (pointing to the pipe), ㉝ (pointing to the pipe), ㉞ (pointing to the pipe), ㉟ (pointing to the pipe), ㊱ (pointing to the pipe), ㊲ (pointing to the pipe), ㊳ (pointing to the pipe), ㊴ (pointing to the pipe), ㊵ (pointing to the pipe), ㊶ (pointing to the pipe), ㊷ (pointing to the pipe), ㊸ (pointing to the pipe), ㊹ (pointing to the pipe), ㊺ (pointing to the pipe), ㊻ (pointing to the pipe), ㊼ (pointing to the pipe), ㊽ (pointing to the pipe), ㊾ (pointing to the pipe), ㊿ (pointing to the pipe). The drawing also includes text: "AC-IN HK1V1.25sq x 2", "アース用 UL1015 AWG16", "1000mm 7-スクリュー付", "水抜き穴", "G, L", and "2-電源穴".


部番	部品名	材質・材厚	数量	備考
1	本体	アルミ合金／SUS	1	粉体焼付塗装
2	LED	LED－6－UNIT	2	－
3	表面グローブ	アクリル（t 3. 0）	1	－
4	専用電源	16W調整	1	－

[illegible]

種 別 照明設備工
細 別 ソーラー照明

(10基) 当り

略図




種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.6/2)^2 \times 3.14 \times 10 = 2.826$	m2	2.83
スパイラルダクト	600	$1.20 \times 10 = 12.000$	m	12.00
スパイラルダクト	500	$0.20 \times 10 = 2.000$	m	2.00
コンクリート	18-8-25	$((0.6/2)^2 \times 1.2 + (0.5/2)^2 \times 0.2 - (0.1016/2)^2 \times 0.2) \times 3.14 \times 10 = 3.767$	m3	3.77
コンクリート金ゴテ仕上げ		$((0.5/2)^2 - (0.1016/2)^2) \times 3.14 \times 10 = 1.881$	m2	1.88
アンカーボルト	4-R-16LN	$4.00 \times 10 = 40.000$	本	40.00
防犯カメラ		$10 = 10.000$	個	10.00
本体	H=3500	$1.00 \times 10 = 10.000$	基	10.00
接地工	D種	$1.00 \times 10 = 10.000$	極	10.00
床掘		$(0.6/2)^2 \times 1.3 \times 3.14 \times 10 = 3.674$	m3	3.67
埋戻し		$3.67 - 3.67 = 0.000$	m3	0.00
残土処分		$(0.6/2)^2 \times 1.3 \times 3.14 \times 10 = 3.674$	m3	3.67

種 別 照明設備工
細 別 引込柱

(10基) 当り

略図




種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.5/2)^2 \times 3.14 \times 10 = 1.963$	m2	1.96
スパイラルダクト	500	$1.20 \times 10 = 12.000$	m	12.00
コンクリート	18-8-25	$((0.6/2)^2 \times 1.2 - (0.1143/2)^2 \times 1.0) \times 3.14 \times 10 = 3.289$	m3	3.29
コンクリート金ゴテ仕上げ		$((0.5/2)^2 - (0.1143/2)^2) \times 3.14 \times 10 = 1.860$	m2	1.86
引込柱	H=6000	$1.00 \times 10 = 10.000$	基	10.00
接地工	D種	$1.00 \times 10 = 10.000$	極	10.00
床掘		$(0.5/2)^2 \times 1.3 \times 3.14 \times 10 = 2.551$	m3	2.55
埋戻し		$2.55 - 2.55 = 0.000$	m3	0.00
残土処分		$(0.5/2)^2 \times 1.3 \times 3.14 \times 10 = 2.551$	m3	2.55

種 別 照明設備工
細 別 分電盤

(10面) 当り

略図




種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$1.1 \times 0.6 \times 10 = 6.600$	m2	6.60
型枠	小型	$(1.0 + 0.5) \times 2 \times 0.5 \times 10 = 15.000$	m2	15.00
コンクリート	18-8-25	$1.0 \times 0.5 \times 0.5 \times 10 = 2.500$	m3	2.50
本体		$1 = 1.000$	基	1.00
床掘		$(1.1 \times 0.6 \times 0.1 + 1.6 \times 1.1 \times 0.3) \times 10 = 5.940$	m3	5.94
埋戻し		$5.94 - 2.16 = 3.780$	m3	3.78
残土処分		$(1.1 \times 0.6 \times 0.1 + 1.0 \times 0.5 \times 0.3) \times 10 = 2.160$	m3	2.16

種 別 照明設備工
細 別 ハンドホール

(10基) 当り

略図



植栽,インターB=(0+300)/2=150

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.82 \times 0.82 \times 10 = 6.724$	m2	6.72
ハンドホール	旧建設省H1-9型 10	$= 10.000$	基	10.00
床掘		$(0.82 \times 0.82 \times 0.1 + 1.12 \times 1.12 \times 1.01) \times 10 = 13.342$	m3	13.34
埋戻し		$13.34 - 5.88 = 4.560$	m3	4.56
残土処分		$(0.82 \times 0.82 \times 0.1 + 0.72 \times 0.72 \times 0.88 + 3.14 \times 0.13 / 12 \times (0.87^2 + 0.87 \times 0.72 + 0.72^2)) \times 10 = 5.881$	m3	5.88


(園路広場整備工)

種 別 舗装工

細 別 透水性インターロッキング舗装B(t=300)

(100m²) 当り


略図



種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	100 = 100.000	m ²	100.00
再生クラッシャーラン路盤	RC-40 t150	100 = 100.000	m ²	100.00
透水シート		100 = 100.000	m ²	100.00
クッション砂	t20	0.02*100 = 2.000	m ³	2.00
透水性 インターロッキングブロック	200×100×80	100 = 100.000	m ²	100.00
		土工事は造成工に含む。		

種 別	舗装工	
細 別	透水性カラーアスファルト舗装A(t=240)	(100m2) 当り


略図



種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	100 = 100.000	m2	100.00
再生クラッシャーラン路盤	RC40 t150	100 = 100.000	m2	100.00
透水性アスコン	t40	100 = 100.000	m2	100.00
カー塗材		100 = 100.000	m2	100.00
		土工事は造成工に含む。		

種 別	舗装工	
細 別	透水性カラーアスファルト舗装B(t=190)	(100m2)当り


略図



種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	100 = 100.000	m2	100.00
再生クラッシャーラン路盤	RC40 t100	100 = 100.000	m2	100.00
透水性アスコン	t40	100 = 100.000	m2	100.00
カラー塗材		100 = 100.000	m2	100.00
		土工事は造成工に含む。		

(100m²) 当り

略图




種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	100 = 100.000	m2	100.00
再生クラッシャーラン路盤	RC40 t100	100 = 100.000	m2	100.00
透水性アスコン	t40	100 = 100.000	m2	100.00
	透水性			
再生ゴムチップ	t40	100 = 100.000	m2	100.00
	透水性			
カラーゴムチップ	t10	100 = 100.000	m2	100.00
		土工事は造成工に含む。		

種別	舗装工
細別	透水性ゴムチップ舗装B(t=250)

(100m²) 当り

略図





種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	100 = 100.000	m2	100.00
再生クラッシャーラン路盤	RC40 t150	100 = 100.000	m2	100.00
透水性アスコン	t40	100 = 100.000	m2	100.00
	透水性			
カラーゴムチップ	t10	100 = 100.000	m2	100.00
		土工事は造成工に含む。		

種 別 舗装工
細 別 誘導ブロック(t=300)

(100m²) 当り

略図




断面図

種 別	規 格	計 算 式	単位	数 量
フィルター層	RC-10 t50	100 = 100.000	m ²	100.00
再生クラッシャーラン路盤	RC-40 t=150	100 = 100.000	m ²	100.00
透水シート		100 = 100.000	m ²	100.00
クッション砂	t20	100*0.02 = 2.000	m ³	2.00
誘導ブロック	透水性 300×300×t80	100 = 100.000	m ²	100.00
		土工事は造成工に含む。		

種 別 園路縁石工
細 別 境界石A

(10m) 当り

略図



断面図


※地先境界ブロックは、目地5mmを考慮して
10m当りの使用個数は16.5個を標準とする。

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.38 \times 10 = 2.000$	m ²	2.00
型枠	小型	$0.1 \times 10 \times 2 = 2.400$	m ²	2.40
コンクリート	18-8-25	$0.38 \times 0.1 \times 10 = 0.216$	m ³	0.22
敷モルタル	1:3(空練り)	$0.15 \times 0.02 \times 10 = 0.015$	m ³	0.02
地先境界ブロックC型	150 × 150 × 600	$10 / 0.605 = 16.500$	本	16.50
		土工事は造成工に含む。		

種 別 園路縁石工
細 別 縁石A

(10m) 当り

略図



断面図


※地先境界ブロックは、目地5mmを考慮して
10m当りの使用個数は16.5個を標準とする。

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.16 \times 10 = 1.600$	m ²	1.60
型枠	小型	$0.1 \times 10 \times 2 = 2.000$	m ²	2.00
コンクリート	18-8-25	$0.16 \times 0.1 \times 10 = 0.160$	m ³	0.16
敷モルタル	1:3(空練り)	$0.12 \times 0.02 \times 10 = 0.024$	m ³	0.02
地先境界ブロックA型	120 × 120 × 600	$10 / 0.605 = 16.500$	本	16.50
		土工事は造成工に含む。		

種 別 園路縁石工
細 別 縁石D

(10m) 当り

略図



断面図


※地先境界ブロックは、目地5mmを考慮して
10m当りの使用個数は16.5個を標準とする。

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.16 \times 10 = 1.600$	m2	1.60
型枠	小型	$0.1 \times 10 \times 2 = 2.000$	m2	2.00
コンクリート	18-8-25	$0.16 \times 0.1 \times 10 = 0.160$	m3	0.16
敷モルタル	1:3(空練り)	$0.12 \times 0.02 \times 10 = 0.024$	m3	0.02
地先境界ブロックA型	120 × 120 × 600	$10 / 0.605 = 16.500$	本	16.50
		土工事は造成工に含む。		

種 別 園路縁石工
細 別 縁石E

(10m) 当り

略図




種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC40 t100	$0.16 \times 10 = 1.600$	m ²	1.60
型枠	小型	$0.1 \times 10 \times 2 = 2.000$	m ²	2.00
コンクリート	18-8-25	$0.16 \times 0.1 \times 10 = 0.160$	m ³	0.16
敷モルタル	1:3(空練り)	$0.12 \times 0.02 \times 10 = 0.024$	m ³	0.02
地先境界ブロックA型	120 × 120 × 600	$10 / 0.605 = 16.500$	本	16.50
		土工事は造成工に含む。		

種 別 園路縁石工
細 別 縁石F

(10m) 当り

略図



断面図

※地先境界ブロックは、目地5mmを考慮して
10m当りの使用個数は16.5個を標準とする。


種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.21 \times 10 = 2.100$	m ²	2.10
型枠	小型	$0.1 \times 10 \times 2 = 2.000$	m ²	2.00
コンクリート	18-8-25	$0.21 \times 0.1 \times 10 = 0.210$	m ³	0.21
敷モルタル	1:3(空練り)	$0.17 \times 0.02 \times 10 = 0.034$	m ³	0.03
地先境界ブロックA型	150/170×120×600	$10 / 0.605 = 16.500$	本	16.50
		土工事は造成工に含む。		

(遊戯施設整備工)

種 別 遊具組立設置工
細 別 児童用複合遊具

(1基) 当り

略図



種 別		遊具組立設置工												
細 別		児童用複合遊具												
(1基) 当り														
■クラッシャーラン基礎(RC-40)										単位:m2				
基礎番号	タテ	ヨコ	高さ	体積	基礎番号	タテ	ヨコ	高さ	体積	基礎番号	タテ	ヨコ	高さ	体積
1	3.60	3.60			41	0.45	0.45		0.203	80	0.90	0.90		0.810
+	1.25	1.20		14.460	42	0.45	0.45		0.203	81	0.90	0.90		0.810
2	2.60	1.90		6.440	43	0.45	0.45		0.203	82	0.90	0.90		0.810
3	2.60	2.60		11.700	44	0.45	0.45		0.203	83	0.80	0.80		0.640
4	1.10	1.10		7.970	45	0.45	0.45		0.203	84	0.80	0.80		0.640
5	2.20	1.40		4.290	46	0.45	0.45		0.203	85	0.80	0.80		0.640
6	1.10	1.10		4.290	47	1.00	1.00		1.000	86	0.80	0.80		0.640
7	1.70	1.10		3.080	48	1.00	1.00		1.000	87	0.70	0.70		0.490
8	1.70	1.10		3.740	49	1.00	1.00		1.000	88	0.70	0.70		0.490
9	0.70	0.40		2.150	50	1.00	1.00		1.000	89	0.70	0.70		0.490
10	0.50	0.50		0.530	51	2.20	1.10			90	0.70	0.70		0.490
11	0.50	0.50		0.500	+	0.60	0.40		2.660	91	0.70	0.70		0.490
12	0.50	0.50		0.500	52	0.50	0.50		0.250	92	0.70	0.70		0.490
13	0.90	0.50		0.700	53	0.50	0.50		0.250	93	0.70	0.70		0.490
14	0.90	0.50		0.900	54	0.50	0.50		0.250	94	0.70	0.70		0.490
15	1.60	1.60		3.010	55	0.50	0.50		0.250	95	0.50	0.50		0.250
16	0.50	0.50		2.810	56	0.50	0.50		0.250	96	0.50	0.50		0.250
17	0.50	0.50		0.500	57	2.10	1.40		2.940	97	0.90	0.60		0.540
18	0.60	0.60		0.610									小計	177.104
19	3.50	3.50		12.610	58	1.10	1.10		1.210	98~103	2.00	2.00		20.000
20	0.70	0.50		12.600	59	1.10	1.10		1.210	104	2.25	3.15		7.088
21	0.70	0.50		0.700	60	1.10	1.10		1.210	105	2.55	4.30		10.965
22	0.90	2.00		2.150	61	1.10	1.10		1.210				小計	38.053
23	1.40	2.90		5.860	62	1.40	1.40		1.960				合計	215.157
24	1.40	2.90		8.120	63	1.30	0.70		0.910					
25	0.40	0.40		4.220	64	1.30	0.70		0.910					
26	0.35	0.35		0.283	65	0.85	0.50		0.425	■均しコンクリート				単位:m3
27	0.35	0.35		0.245	66	0.50	0.50		0.250	177.104	× 0.05			8.855
28	0.59	0.35		0.329	67	0.50	0.50		0.250				=	8.855
29	0.85	0.50		0.632	68	0.70	0.40		0.280					
30	2.00	2.20			69	2.10	1.10		2.310	■型枠(均しコンクリート用)				単位:m2
-	0.15	0.28		4.359	70	2.10	1.10		2.310	延長	タテ	ヨコ		
31	0.50	0.50		0.250	71	2.10	1.10		2.310		103.09	89.08		
32	0.50	0.50		0.250	72	2.10	1.10		2.310		0.20	-0.30		
33	0.60	0.50		0.300	73	2.10	1.10		2.310		-0.60	0.40		
34	0.60	0.50		0.300	74	2.10	1.10		2.310		102.69	89.18		
35	0.45	0.45		0.203	75	0.80	1.60		1.280	(タテ+ヨコ) × 0.05				
36	0.45	0.45		0.203	76	0.90	1.25		1.125					9.593
37	0.45	0.45		0.203	77	3.10	0.90		2.790				=	9.593
38	0.45	0.45		0.203	78	3.10	0.90		2.790					
39	0.45	0.45		0.203	79	0.90	0.90		0.810					
40	0.45	0.45		0.203										

種 別		遊具組立設置工												
細 別		児童用複合遊具												
(1基) 当り														
■コンクリート										単位:m3				
基礎番号	タテ	ヨコ	高さ	体積	基礎番号	タテ	ヨコ	高さ	体積	基礎番号	タテ	ヨコ	高さ	体積
1	3.50	3.50	0.70		41	0.35	0.35	0.40	0.049	80	0.80	0.80	0.35	0.224
+	1.20	1.10	0.70	9.499	42	0.35	0.35	0.40	0.049	81	0.80	0.80	0.35	0.224
2	2.50	1.80	0.70	3.150	43	0.35	0.35	0.40	0.049	82	0.80	0.80	0.35	0.224
3	2.50	2.50	0.70	4.375	44	0.35	0.35	0.40	0.049	83	0.70	0.70	0.35	0.172
4	1.00	1.00	0.70	0.700	45	0.35	0.35	0.40	0.049	84	0.70	0.70	0.35	0.172
5	2.10	1.3	0.70	1.911	46	0.35	0.35	0.40	0.049	85	0.70	0.70	0.35	0.172
6	1.00	1.00	0.70	0.700	47	0.90	0.90	0.35	0.284	86	0.70	0.70	0.35	0.172
7	1.60	1.00	0.70	1.120	48	0.90	0.90	0.35	0.284	87	0.60	0.60	0.35	0.126
8	1.60	1.00	0.70	1.120	49	0.90	0.90	0.35	0.284	88	0.60	0.60	0.35	0.126
9	0.60	0.30	0.50	0.090	50	0.90	0.90	0.35	0.284	89	0.60	0.60	0.35	0.126
10	0.40	0.40	0.50	0.080	51	2.10	1.00	0.70		90	0.60	0.60	0.35	0.126
11	0.40	0.40	0.50	0.080	+	0.40	0.30	0.70	1.554	91	0.60	0.60	0.35	0.126
12	0.40	0.40	0.50	0.080	52	0.40	0.40	0.50	0.080	92	0.60	0.60	0.35	0.126
13	0.80	0.40	0.25	0.080	53	0.40	0.40	0.50	0.080	93	0.60	0.60	0.35	0.126
14	0.80	0.40	0.25	0.080	54	0.40	0.40	0.50	0.080	94	0.60	0.60	0.35	0.126
15	1.50	1.50	0.50	1.125	55	0.40	0.40	0.50	0.080	95	0.40	0.40	0.60	0.096
16	0.40	0.40	0.50	0.080	56	0.40	0.40	0.50	0.080	96	0.40	0.40	0.60	0.096
17	0.40	0.40	0.40	0.064	57	2.00	1.30	0.70	1.820	97	0.80	0.50	0.50	0.200
18	0.50	0.50	0.50	0.125									合計	66.636
19	3.40	3.40	0.70	8.092	58	1.00	1.00	0.70	0.700					
20	0.60	0.40	0.25	0.060	59	1.00	1.00	0.70	0.700					
21	0.60	0.40	0.25	0.060	60	1.00	1.00	0.70	0.700					
22	0.80	1.90	0.70	1.064	61	1.00	1.00	0.70	0.700					
23	1.30	2.80	0.70	2.548	62	1.30	1.30	0.50	0.845					
24	1.30	2.80	0.70	2.548	63	1.20	0.60	0.70	0.504					
25	0.30	0.30	0.50	0.045	64	1.20	0.60	0.70	0.504					
26	0.25	0.25	0.50	0.031	65	0.75	0.40	0.50	0.150					
27	0.25	0.25	0.50	0.031	66	0.40	0.40	0.50	0.080					
28	0.49	0.25	0.50	0.061	67	0.40	0.40	0.50	0.080					
29	0.75	0.40	0.25	0.075	68	0.60	0.30	0.50	0.090					
30	1.90	2.10	0.70		69	2.00	1.00	0.70	1.400					
-	0.25	0.48	0.70	2.710	70	2.00	1.00	0.70	1.400					
31	0.40	0.40	0.25	0.040	71	2.00	1.00	0.70	1.400					
32	0.40	0.40	0.25	0.040	72	2.00	1.00	0.70	1.400					
33	0.50	0.40	0.25	0.050	73	2.00	1.00	0.70	1.400					
34	0.50	0.40	0.25	0.050	74	2.00	1.00	0.70	1.400					
35	0.35	0.35	0.40	0.049	75	0.70	1.50	0.70	0.735					
36	0.35	0.35	0.40	0.049	76	0.80	1.15	0.35	0.322					
37	0.35	0.35	0.40	0.049	77	3.00	0.80	0.35	0.840					
38	0.35	0.35	0.40	0.049	78	3.00	0.80	0.35	0.840					
39	0.35	0.35	0.40	0.049	79	0.80	0.80	0.35	0.224					
40	0.35	0.35	0.40	0.049										

種 別		遊具組立設置工																	
細 別		児童用複合遊具										(1基) 当り							
■型枠															単位:m2				
基礎番号	タテ	ヨコ	高さ	表面積	基礎番号	タテ	ヨコ	高さ	表面積	基礎番号	タテ	ヨコ	高さ	表面積					
1	3.50	3.50	0.70		41	0.35	0.35	0.40	0.560	80	0.80	0.80	0.35	1.120					
+	1.20	1.10	0.70	11.340	42	0.35	0.35	0.40	0.560	81	0.80	0.80	0.35	1.120					
2	2.50	1.80	0.70	6.020	43	0.35	0.35	0.40	0.560	82	0.80	0.80	0.35	1.120					
3	2.50	2.50	0.70	7.000	44	0.35	0.35	0.40	0.560	83	0.70	0.70	0.35	0.980					
4	1.00	1.00	0.70	2.800	45	0.35	0.35	0.40	0.560	84	0.70	0.70	0.35	0.980					
5	2.10	1.3	0.70	4.760	46	0.35	0.35	0.40	0.560	85	0.70	0.70	0.35	0.980					
6	1.00	1.00	0.70	2.800	47	0.90	0.90	0.35	1.260	86	0.70	0.70	0.35	0.980					
7	1.60	1.00	0.70	3.640	48	0.90	0.90	0.35	1.260	87	0.60	0.60	0.35	0.840					
8	1.60	1.00	0.70	3.640	49	0.90	0.90	0.35	1.260	88	0.60	0.60	0.35	0.840					
9	0.60	0.30	0.50	0.900	50	0.90	0.90	0.35	1.260	89	0.60	0.60	0.35	0.840					
10	0.40	0.40	0.50	0.800	51	2.10	1.00	0.70		90	0.60	0.60	0.35	0.840					
11	0.40	0.40	0.50	0.800	+	0.40	0.30	0.70	4.760	91	0.60	0.60	0.35	0.840					
12	0.40	0.40	0.50	0.800	52	0.40	0.40	0.50	0.800	92	0.60	0.60	0.35	0.840					
13	0.80	0.40	0.25	0.600	53	0.40	0.40	0.50	0.800	93	0.60	0.60	0.35	0.840					
14	0.80	0.40	0.25	0.600	54	0.40	0.40	0.50	0.800	94	0.60	0.60	0.35	0.840					
15	1.50	1.50	0.50	3.000	55	0.40	0.40	0.50	0.800	95	0.40	0.40	0.60	0.960					
16	0.40	0.40	0.50	0.800	56	0.40	0.40	0.50	0.800	96	0.40	0.40	0.60	0.960					
17	0.40	0.40	0.40	0.640	57	2.00	1.30	0.70	4.620	97	0.80	0.50	0.50	1.300					
18	0.50	0.50	0.50	1.000									合計	189.220					
19	3.40	3.40	0.70	9.520	58	1.00	1.00	0.70	2.800										
20	0.60	0.40	0.25	0.500	59	1.00	1.00	0.70	2.800										
21	0.60	0.40	0.25	0.500	60	1.00	1.00	0.70	2.800										
22	0.80	1.90	0.70	3.780	61	1.00	1.00	0.70	2.800										
23	1.30	2.80	0.70	5.740	62	1.30	1.30	0.50	2.600										
24	1.30	2.80	0.70	5.740	63	1.20	0.60	0.70	2.520										
25	0.30	0.30	0.50	0.600	64	1.20	0.60	0.70	2.520										
26	0.25	0.25	0.50	0.500	65	0.75	0.40	0.50	1.150										
27	0.25	0.25	0.50	0.500	66	0.40	0.40	0.50	0.800										
28	0.49	0.25	0.50	0.740	67	0.40	0.40	0.50	0.800										
29	0.75	0.40	0.25	0.575	68	0.60	0.30	0.50	0.900										
30	1.90	2.10	0.70		69	2.00	1.00	0.70	4.200										
-	0.25	0.48	0.70	5.950	70	2.00	1.00	0.70	4.200										
31	0.40	0.40	0.25	0.400	71	2.00	1.00	0.70	4.200										
32	0.40	0.40	0.25	0.400	72	2.00	1.00	0.70	4.200										
33	0.50	0.40	0.25	0.450	73	2.00	1.00	0.70	4.200										
34	0.50	0.40	0.25	0.450	74	2.00	1.00	0.70	4.200										
35	0.35	0.35	0.40	0.560	75	0.70	1.50	0.70	3.080										
36	0.35	0.35	0.40	0.560	76	0.80	1.15	0.35	1.365										
37	0.35	0.35	0.40	0.560	77	3.00	0.80	0.35	2.660										
38	0.35	0.35	0.40	0.560	78	3.00	0.80	0.35	2.660										
39	0.35	0.35	0.40	0.560	79	0.80	0.80	0.35	1.120										
40	0.35	0.35	0.40	0.560															

種 別		遊具組立設置工								(1基) 当り				
細 別		児童用複合遊具												
■床掘り														
単位:m2														
基礎番号	タテ	ヨコ	高さ	体積	基礎番号	タテ	ヨコ	高さ	体積	基礎番号	タテ	ヨコ	高さ	体積
1	4.10	4.10	0.70		41	0.95	0.95	0.40	0.903	80	1.40	1.40	0.35	1.960
+	1.10	1.80	0.70	18.790	42	0.95	0.95	0.40	0.903	81	1.40	1.40	0.35	1.960
2	3.10	2.40	0.70	16.560	43	0.95	0.95	0.40	0.903	82	1.40	1.40	0.35	1.960
3	3.10	3.10	0.70	16.560	44	0.95	0.95	0.40	0.903	83	1.30	1.30	0.35	1.690
4	1.60	1.60	0.70	16.560	45	0.95	0.95	0.40	0.903	84	1.30	1.30	0.35	1.690
5	2.70	1.90	0.70	16.560	46	0.95	0.95	0.40	0.903	85	1.30	1.30	0.35	1.690
6	1.60	1.60	0.70	16.560	47	1.50	1.50	0.35	2.250	86	1.30	1.30	0.35	1.690
7	2.20	1.60	0.70	16.560	48	1.50	1.50	0.35	2.250	87	1.20	1.20	0.35	1.440
8	2.20	1.60	0.70	16.560	49	1.50	1.50	0.35	2.250	88	1.20	1.20	0.35	1.440
9	1.20	0.90	0.50	16.560	50	1.50	1.50	0.35	2.250	89	1.20	1.20	0.35	1.440
10	1.00	1.00	0.50	16.560	51	2.70	1.60	0.70		90	1.20	1.20	0.35	1.440
11	1.00	1.00	0.50	16.560	+	0.20	0.10	0.70	4.340	91	1.20	1.20	0.35	1.440
12	1.00	1.00	0.50	16.560	52	1.00	1.00	0.50	1.000	92	1.20	1.20	0.35	1.440
13	1.40	1.00	0.25	16.560	53	1.00	1.00	0.50	1.000	93	1.20	1.20	0.35	1.440
14	1.40	1.00	0.25	16.560	54	1.00	1.00	0.50	1.000	94	1.20	1.20	0.35	1.440
15	2.10	2.10	0.50	16.560	55	1.00	1.00	0.50	1.000	95	1.00	1.00	0.60	1.000
16	1.00	1.00	0.50	16.560	56	1.00	1.00	0.50	1.000	96	1.00	1.00	0.60	1.000
17	1.00	1.00	0.40	16.560	57	2.60	1.90	0.70	4.940	97	1.40	1.10	0.50	1.540
18	1.10	1.10	0.50	16.560									小計	619.996
19	4.00	4.00	0.70	16.560	58	1.60	1.60	0.70	2.560		2.00	2.00	0.03	0.600
20	1.20	1.00	0.25	16.560	59	1.60	1.60	0.70	2.560		2.25	3.15	0.03	0.213
21	1.20	1.00	0.25	16.560	60	1.60	1.60	0.70	2.560		2.55	4.30	0.03	0.329
22	1.40	2.50	0.70	16.560	61	1.60	1.60	0.70	2.560				小計	1.142
23	1.90	3.40	0.70	16.560	62	1.90	1.90	0.50	3.610				合計	621.138
24	1.90	3.40	0.70	16.560	63	1.80	1.20	0.70	2.160					
25	0.90	0.90	0.50	16.560	64	1.80	1.20	0.70	2.160					
26	0.85	0.85	0.50	16.560	65	1.35	1.00	0.50	1.350					
27	0.85	0.85	0.50	16.560	66	1.00	1.00	0.50	1.000					
28	1.09	0.85	0.50	16.560	67	1.00	1.00	0.50	1.000					
29	1.35	1.00	0.25	16.560	68	1.20	0.90	0.50	1.080					
30	2.50	2.70	0.70		69	2.60	1.60	0.70	4.160					
-	-0.10	-0.20	0.70	6.730	70	2.60	1.60	0.70	4.160					
31	1.00	1.00	0.25	1.000	71	2.60	1.60	0.70	4.160					
32	1.00	1.00	0.25	1.000	72	2.60	1.60	0.70	4.160					
33	1.10	1.00	0.25	1.100	73	2.60	1.60	0.70	4.160					
34	1.10	1.00	0.25	1.100	74	2.60	1.60	0.70	4.160					
35	0.95	0.95	0.40	0.903	75	1.30	2.10	0.70	2.730					
36	0.95	0.95	0.40	0.903	76	1.40	1.75	0.35	2.450					
37	0.95	0.95	0.40	0.903	77	3.60	1.40	0.35	5.040					
38	0.95	0.95	0.40	0.903	78	3.60	1.40	0.35	5.040					
39	0.95	0.95	0.40	0.903	79	1.40	1.40	0.35	1.960					
40	0.95	0.95	0.40	0.903										

種 別		遊具組立設置工																		
細 別		児童用複合遊具																		
■鉄筋																				
基礎番号	長さ		本数		小計	基礎番号	長さ		本数		小計	基礎番号	長さ		本数		小計			
61	0.85	×	5	×	2	8.50	74	0.85	×	11	×	2	18.70	85	0.55	×	4	×	2	4.40
	0.55	×	5	×	2	5.50		0.55	×	11	×	2	12.10		0.20	×	4	×	2	1.60
	0.85	×	5	×	2	8.50		1.85	×	5	×	2	18.50		0.55	×	4	×	2	4.40
	0.55	×	5	×	2	5.50		0.55	×	5	×	2	5.50		0.20	×	4	×	2	1.60
	3.40	×	2			6.80		5.40	×	2			10.80	86	0.55	×	4	×	2	4.40
62	なし						75	1.35	×	3	×	2	8.10		0.20	×	4	×	2	1.60
63	0.45	×	6	×	2	5.40		0.55	×	3	×	2	3.30		0.55	×	4	×	2	4.40
	0.55	×	6	×	2	6.60		0.55	×	7	×	2	7.70		0.20	×	4	×	2	1.60
	1.05	×	3	×	2	6.30		0.55	×	7	×	2	7.70	87	0.45	×	4	×	2	3.60
	0.55	×	3	×	2	3.30		3.80	×	2			7.60		0.20	×	4	×	2	1.60
	3.00	×	2			6.00	76	なし							0.45	×	4	×	2	3.60
64	0.45	×	6	×	2	5.40	77	0.65	×	15	×	2	19.50		0.20	×	4	×	2	1.60
	0.55	×	6	×	2	6.60		0.20	×	15	×	2	6.00	88	0.45	×	4	×	2	3.60
	1.05	×	3	×	2	6.30		2.85	×	4	×	2	22.80		0.20	×	4	×	2	1.60
	0.55	×	3	×	2	3.30		0.20	×	4	×	2	1.60		0.45	×	4	×	2	3.60
	3.00	×	2			6.00	78	0.65	×	15	×	2	19.50		0.20	×	4	×	2	1.60
65	なし							0.20	×	15	×	2	6.00	89	0.45	×	4	×	2	3.60
66	なし							2.85	×	4	×	2	22.80		0.20	×	4	×	2	1.60
67	なし							0.20	×	4	×	2	1.60		0.45	×	4	×	2	3.60
68	なし						79	0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
69	0.85	×	11	×	2	18.70		0.20	×	4	×	2	1.60	90	0.45	×	4	×	2	3.60
	0.55	×	11	×	2	12.10		0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
	1.85	×	5	×	2	18.50		0.20	×	4	×	2	1.60		0.45	×	4	×	2	3.60
	0.55	×	5	×	2	5.50	80	0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
	5.40	×	2			10.80		0.20	×	4	×	2	1.60	91	0.45	×	4	×	2	3.60
70	0.85	×	11	×	2	18.70		0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
	0.55	×	11	×	2	12.10		0.20	×	4	×	2	1.60		0.45	×	4	×	2	3.60
	1.85	×	5	×	2	18.50	81	0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
	0.55	×	5	×	2	5.50		0.20	×	4	×	2	1.60	92	0.45	×	4	×	2	3.60
	5.40	×	2			10.80		0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
71	0.85	×	11	×	2	18.70		0.20	×	4	×	2	1.60		0.45	×	4	×	2	3.60
	0.55	×	11	×	2	12.10	82	0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
	1.85	×	5	×	2	18.50		0.20	×	4	×	2	1.60	93	0.45	×	4	×	2	3.60
	0.55	×	5	×	2	5.50		0.65	×	4	×	2	5.20		0.20	×	4	×	2	1.60
	5.40	×	2			10.80		0.20	×	4	×	2	1.60		0.45	×	4	×	2	3.60
72	0.85	×	11	×	2	18.70	83	0.55	×	4	×	2	4.40		0.20	×	4	×	2	1.60
	0.55	×	11	×	2	12.10		0.20	×	4	×	2	1.60	94	0.45	×	4	×	2	3.60
	1.85	×	5	×	2	18.50		0.55	×	4	×	2	4.40		0.20	×	4	×	2	1.60
	0.55	×	5	×	2	5.50		0.20	×	4	×	2	1.60		0.45	×	4	×	2	3.60
	5.40	×	2			10.80	84	0.55	×	4	×	2	4.40		0.20	×	4	×	2	1.60
73	0.85	×	11	×	2	18.70		0.20	×	4	×	2	1.60	95	なし					
	0.55	×	11	×	2	12.10		0.55	×	4	×	2	4.40	96	なし					
	1.85	×	5	×	2	18.50		0.20	×	4	×	2	1.60	97	なし					
	0.55	×	5	×	2	5.50											合計		2655.10	
	5.40	×	2			10.80														

[illegible]


種 別 遊具組立設置工
細 別 幼児用複合遊具

(1基) 当り

略図


基礎数量表					
	A	B	D	H	数
⑦	600	600	150	450	9
⑧	400	400	150	450	4
⑨	350	350	150	450	4
⑩	300	300	150	450	2
⑪	200	430	150	200	1

躯体の床掘深さ=150+200=350
A: 0.824㎡



躯体の床掘深さ=150+450=600
A: 15.73㎡

基礎伏図 S=1:50



基礎詳細図 S=1:20


植栽=0

[illegible]

種 別 遊具組立設置工
細 別 半球ステップ

(10基) 当り

略図




植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.576^2 \times 3.142 / 4) \times 10 = 2.606$	m2	2.61
型枠		$(0.576 \times 3.142 \times 0.05) \times 10 = 0.905$	m2	0.90
コンクリート	18-8-25	$(0.576^2 \times 3.142 / 4 \times 0.05) \times 10 = 0.130$	m3	0.13
本体		$10 = 10.000$	基	10.00
床掘		$((0.676/2)^2 \times 3.14 \times 0.1 + (1.176/2)^2 \times 3.14 \times 0.05) \times 10 = 0.902$	m3	0.90
埋戻し		$0.902 - 0.489 = 0.413$	m3	0.41
残土処分		$((0.676/2)^2 \times 3.14 \times 0.1 + (0.576/2)^2 \times 3.14 \times 0.05) \times 10 = 0.489$	m3	0.49

種 別 遊具組立設置工
細 別 平均台

(10基) 当り

略図





植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.35 \times 0.35 \times 4) \times 10 = 4.900$	m2	4.90
型枠	均し	$(0.05 \times 0.35 \times 4 \times 4) \times 10 = 2.800$	m2	2.80
均しコンクリート	18-8-25	$(0.35 \times 0.35 \times 0.05 \times 4) \times 10 = 0.245$	m3	0.25
本体		$10 = 10.000$	基	10.00
床掘		$(0.35 \times 0.35 \times 0.1 \times 4 + 2.13 \times 1.13 \times 0.35) \times 10 = 8.914$	m3	8.91
埋戻し		$8.914 - 0.769 = 8.145$	m3	8.14
残土処分		$(0.35 \times 0.35 \times 0.15 + (0.0605 / 2)^2 \times 3.14 \times 0.3) \times 4 \times 10 = 0.769$	m3	0.77

種 別 遊具組立設置工
細 別 日よけ付き砂場

(10基) 当り

略図





植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.6 \times 0.6 \times 4) \times 10 = 14.400$	m2	14.40
型枠	小型	$(0.5 \times 0.5 \times 4 \times 4) \times 10 = 40.000$	m2	40.00
コンクリート	18-8-25	$(0.5 \times 0.5 \times 0.5 \times 4) \times 10 = 5.000$	m3	5.00
本体		$10 = 10.000$	基	10.00
床掘		$(0.6 \times 0.6 \times 0.1 + 1.1 \times 1.1 \times 0.6) \times 4 \times 10 = 30.480$	m3	30.48
埋戻し		$30.480 - 6.458 = 24.022$	m3	24.02
残土処分		$(0.6 \times 0.6 \times 0.1 + 0.5 \times 0.5 \times 0.5 + (0.0763/2)^2 \times 3.14 \times 0.1) \times 4 \times 10 = 6.458$	m3	6.46

種 別 遊具組立設置工
細 別 幼児用ブランコ

(10基) 当り

略図



正面図

植栽=0


種 別		遊具組立設置工			
細 別		幼児用ブランコ	(10基)	当り	
種 別	規 格	計 算 式	単位	数	量
再生クラッシャーラン基礎	RC-40 t=100	$(0.45 \times 0.45 \times 4) * 10 = 8.100$	m2	8.10	
型枠	均し	$(0.45 \times 0.05 \times 4) * 4 * 10 = 3.600$	m2	3.60	
均しコンクリート	18-8-25	$(0.45 \times 0.45 \times 0.05) * 4 * 10 = 0.405$	m3	0.41	
型枠		$(0.35 \times 0.35 \times 4) * 4 * 10 = 19.600$	m2	19.60	
コンクリート	18-8-25	$(0.35 \times 0.35 \times 0.35) * 4 * 10 = 1.715$	m3	1.72	
ブランコ本体		$10 = 10.000$	基	10.00	
床掘		$(0.45 \times 0.45 \times 0.1 + 0.95 \times 0.95 \times 0.55) * 4 * 10 = 20.665$	m3	20.67	
埋戻し		$20.665 - 2.930 = 17.735$	m3	17.74	
残土処分		$(0.45 \times 0.45 \times 0.15 + 0.35 \times 0.35 \times 0.35) * 4 * 10 = 2.930$	m3	2.93	

種 別		遊具組立設置工			
細 別		幼児用ブランコ安全柵 (10基)当り			
種 別	規 格	計 算 式		単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.3*0.3*16)*10 = 14.400$		m2	14.40
型枠	均し	$(0.30*0.05*4)*16*10 = 9.600$		m2	9.60
均しコンクリート	18-8-25	$(0.3*0.3*0.05)*16*10 = 0.720$		m3	0.72
型枠		$(0.3*0.2*4)*16*10 = 38.400$		m2	38.40
コンクリート	18-8-25	$(0.2*0.2*0.3)*16*10 = 1.920$		m3	1.92
柵本体		$10 = 10.000$		組	10.00

種 別 遊具組立設置工
細 別 ロッキング遊具A

(10基) 当り

略図




ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.7 \times 0.7 \times 10 = 4.900$	m2	4.90
型枠	小型	$(0.6 \times 0.4 \times 4) \times 10 = 9.600$	m2	9.60
コンクリート	18-8-25	$0.6 \times 0.6 \times 0.4 \times 10 = 1.440$	m3	1.44
本体	キリン 913 × 840 × t19	$10 = 10.000$	基	10.00
床掘		$(0.7 \times 0.7 \times 0.1 + 1.2 \times 1.2 \times 0.56) \times 10 = 8.554$	m3	8.55
埋戻し		$8.554 - 1.940 = 6.614$	m3	6.61
残土処分		$(0.7 \times 0.7 \times 0.1 + 0.6 \times 0.6 \times 0.4 + 0.1 \times 0.05 \times 0.2) \times 10 = 1.940$	m3	1.94

種 別 遊具組立設置工
細 別 ロッキング遊具B

(10基) 当り

略図




ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.7 \times 0.7 \times 10 = 4.900$	m2	4.90
型枠	小型	$(0.6 \times 0.4 \times 4) \times 10 = 9.600$	m2	9.60
コンクリート	18-8-25	$0.6 \times 0.6 \times 0.4 \times 10 = 1.440$	m3	1.44
本体	ゾウ 830×790×t19	$10 = 10.000$	基	10.00
床掘		$(0.7 \times 0.7 \times 0.1 + 1.2 \times 1.2 \times 0.56) \times 10 = 8.554$	m3	8.55
埋戻し		$8.554 - 1.940 = 6.614$	m3	6.61
残土処分		$(0.7 \times 0.7 \times 0.1 + 0.6 \times 0.6 \times 0.4 + 0.1 \times 0.05 \times 0.2) \times 10 = 1.940$	m3	1.94

種 別 遊具組立設置工
細 別 ロッキング遊具C

(10基) 当り

略図




ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.7 \times 0.7 \times 10 = 4.900$	m2	4.90
型枠	小型	$(0.6 \times 0.4 \times 4) \times 10 = 9.600$	m2	9.60
コンクリート	18-8-25	$0.6 \times 0.6 \times 0.4 \times 10 = 1.440$	m3	1.44
サイ				
本体	845 × 630 × t19	$10 = 10.000$	基	10.00
床掘		$(0.7 \times 0.7 \times 0.1 + 1.2 \times 1.2 \times 0.56) \times 10 = 8.554$	m3	8.55
埋戻し		$8.554 - 1.940 = 6.614$	m3	6.61
残土処分		$(0.7 \times 0.7 \times 0.1 + 0.6 \times 0.6 \times 0.4 + 0.1 \times 0.05 \times 0.2) \times 10 = 1.940$	m3	1.94

種 別 遊具組立設置工
細 別 ロッキング遊具D

(10基) 当り

略図




ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.7 \times 0.7 \times 10 = 4.900$	m2	4.90
型枠	小型	$(0.6 \times 0.4 \times 4) \times 10 = 9.600$	m2	9.60
コンクリート	18-8-25	$0.6 \times 0.6 \times 0.4 \times 10 = 1.440$	m3	1.44
カバ				
本体	857 × 740 × t19	$10 = 10.000$	基	10.00
床掘		$(0.7 \times 0.7 \times 0.1 + 1.2 \times 1.2 \times 0.56) \times 10 = 8.554$	m3	8.55
埋戻し		$8.554 - 1.940 = 6.614$	m3	6.61
残土処分		$(0.7 \times 0.7 \times 0.1 + 0.6 \times 0.6 \times 0.4 + 0.1 \times 0.05 \times 0.2) \times 10 = 1.940$	m3	1.94

種 別 遊具組立設置工
細 別 回転遊具

(10基) 当り

略図



外観図


植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$1.1 \times 1.1 \times 10 = 12.100$	m2	12.10
型枠	均し	$(1.1 \times 0.05 \times 4) \times 10 = 2.200$	m2	2.20
均しコンクリート	18-8-25	$1.1 \times 1.1 \times 0.05 \times 10 = 0.605$	m3	0.61
型枠	小型	$1.0 \times 0.3 \times 4 \times 10 = 12.000$	m2	12.00
コンクリート	18-8-25	$1.0 \times 1.0 \times 0.3 \times 10 = 3.000$	m3	3.00
本体		$10 = 10.000$	基	10.00
床掘		$(1.1 \times 1.1 \times 0.1 + 1.6 \times 1.6 \times 0.35) \times 10 = 10.170$	m3	10.17
埋戻し		$10.170 - 4.815 = 5.355$	m3	5.36
残土処分		$(1.1 \times 1.1 \times 0.15 + 1.0 \times 1.0 \times 0.3) \times 10 = 4.815$	m3	4.82

種 別 遊具組立設置工
細 別 遊具外周サークルベンチ

(10基) 当り

略図




透水性ゴムチップ舗装A=240

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.5 \times 0.5 \times 13 \times 10 = 32.500$	m2	32.50
型枠	均し	$(0.5 \times 0.05 \times 4 \times 13) \times 10 = 13.000$	m2	13.00
均しコンクリート	18-8-25	$(0.5 \times 0.5 \times 0.05 \times 13) \times 10 = 1.625$	m3	1.63
型枠	小型	$(0.4 \times 0.3 \times 4 \times 13) \times 10 = 62.400$	m2	62.40
コンクリート	18-8-25	$(0.4 \times 0.4 \times 0.3 - (0.0891/2)^2 \times 3.14) \times 13 \times 10 = 5.430$	m3	5.43
本体		$10 = 10.000$	基	10.00
床掘		$(0.5 \times 0.5 \times 0.1 + 1.0 \times 1.0 \times 0.21) \times 13 \times 10 = 30.550$	m3	30.55
埋戻し		$30.550 - 9.243 = 21.307$	m3	21.31
残土処分		$(0.5 \times 0.5 \times 0.15 + 0.4 \times 0.4 \times 0.21) \times 13 \times 10 = 9.243$	m3	9.24

種 別 遊具組立設置工
細 別 砂場テーブル

(10基) 当り

略図




植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$1.35 \times 0.7 \times 10 = 9.450$	m2	9.45
型枠	小型	$(1.25 \times 0.25 \times 2 + 0.6 \times 0.25 \times 2) \times 10 = 9.250$	m2	9.25
コンクリート	18-8-25	$(1.25 \times 0.6 \times 0.25) \times 10 = 1.875$	m3	1.88
本体		$10 = 10.000$	基	10.00
床掘		$(1.35 \times 0.7 \times 0.1 + 1.85 \times 1.2 \times 0.4) \times 10 = 9.825$	m3	9.83
埋戻し		$9.825 - 2.820 = 7.005$	m3	7.01
残土処分		$(1.35 \times 0.7 \times 0.1 + 1.25 \times 0.6 \times 0.25) \times 10 = 2.820$	m3	2.82

種 別 健康遊具設置工
細 別 健康遊具A

(10基) 当り

略図



ダスト=40


種 別	規 格	計 算 式	単位	数 量
再生クラッシュラン基礎	RC-40 t=100	$(0.35 \times 0.5) \times 2 \times 10$	m2	3.50
型枠	均し	$(0.35 \times 0.05 \times 2 + 0.5 \times 0.05 \times 2) \times 2 \times 10$	m2	1.70
均しコンクリート	18-8-25	$(0.35 \times 0.5 \times 0.05) \times 2 \times 10$	m3	0.18
型枠	小型	$(0.25 \times 0.3 \times 2 + 0.4 \times 0.3 \times 2) \times 2 \times 10$	m2	7.80
コンクリート	18-8-25	$(0.25 \times 0.4 - (0.15/2)^2 \times 3.14) \times 0.3 \times 2 \times 10$	m3	0.49
モルタル	1:3	$((0.15/2)^2 - (0.0605/2)^2) \times 3.14 \times 0.3 \times 2 \times 10$	m3	0.09
本体	1800 × 420 × 700	10	基	10.00
床掘		$(0.35 \times 0.5 \times 0.1 + 0.85 \times 1.0 \times 0.41) \times 2 \times 10$	m3	7.32
埋戻し		7.320 - 1.125	m3	6.20
残土処分		$(0.35 \times 0.5 \times 0.15 + 0.25 \times 0.4 \times 0.3) \times 2 \times 10$	m3	1.13

種 別 健康遊具設置工

細 別 健康遊具C

(10基) 当り

略図




ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$1.1 \times 0.7 \times 10 = 7.700$	m2	7.70
型枠	均し	$(1.1 \times 0.05 \times 2 + 0.7 \times 0.05 \times 2) \times 10 = 1.800$	m2	1.80
均しコンクリート	18-8-25	$1.1 \times 0.7 \times 0.05 \times 10 = 0.385$	m3	0.39
型枠	小型	$(1.0 \times 0.4 \times 2 + 0.6 \times 0.4 \times 2) \times 10 = 12.800$	m2	12.80
コンクリート	18-8-25	$(1.0 \times 0.6 - (0.2/2)^2 \times 3.14 \times 2) \times 0.4 \times 10 = 2.149$	m3	2.15
モルタル	1:3	$((0.2/2)^2 - (0.0605/2)^2) \times 3.14 \times 0.4 \times 2 \times 10 = 0.228$	m3	0.23
本体	600×400×2000	$10 = 10.000$	基	10.00
床掘		$(1.1 \times 0.7 \times 0.1 + 1.6 \times 1.2 \times 0.51) \times 10 = 10.562$	m3	10.56
埋戻し		$10.562 - 3.555 = 7.007$	m3	7.01
残土処分		$(1.1 \times 0.7 \times 0.15 + 1.0 \times 0.6 \times 0.4) \times 10 = 3.555$	m3	3.56

種 別 健康遊具設置工
細 別 健康遊具D

(10基) 当り

略図



基礎伏図



ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャー基礎	RC-40 t=100	$(0.4 \times 0.4 \times 3) \times 10$	m2	4.80
型枠	均し	$(0.4 \times 0.05 \times 4 \times 3) \times 10$	m2	2.40
均しコンクリート	18-8-25	$(0.4 \times 0.4 \times 0.05 \times 3) \times 10$	m3	0.24
型枠	小型	$(0.3 \times 0.4 \times 4 \times 3) \times 10$	m2	14.40
コンクリート	18-8-25	$(0.3 \times 0.3 - (0.2/2)^2 \times 3.14) \times 0.4 \times 3 \times 10$	m3	0.70
モルタル	1:3	$((0.2/2)^2 - (0.0605/2)^2) \times 3.14 \times 0.4 \times 3 \times 10$	m3	0.34
本体	990 × 645 × 1100	10	基	10.00
床掘		$(0.4 \times 0.4 \times 0.1 \times 3 + (0.9 \times 0.9 \times 3 - 0.405 \times 0.735 \times 2) \times 0.51) \times 10$	m3	9.84
埋戻し		9.837 - 1.800	m3	8.04
残土処分		$(0.4 \times 0.4 \times 0.15 + 0.3 \times 0.3 \times 0.4) \times 3 \times 10$	m3	1.80

種 別 健康遊具設置工
細 別 健康遊具E

(10基) 当り

略図



基礎伏図


ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャー基礎	RC-40 t=100	$(0.65 \times 0.65 + 0.4 \times 0.4 \times 3) \times 10$	m2	9.03
型枠	均し	$(0.4 \times 0.05 \times 4 \times 3) \times 10$	m2	2.40
均しコンクリート	18-8-25	$(0.4 \times 0.4 \times 0.05 \times 3) \times 10$	m3	0.24
型枠	小型	$(0.55 \times 0.35 \times 4 + 0.3 \times 0.3 \times 4 \times 3) \times 10$	m2	18.50
コンクリート	18-8-25	$(0.3 \times 0.3 \times 0.3 \times 3 + 0.55 \times 0.55 \times 0.35 - (0.15/2)^2 \times 3.14 \times 0.3 \times 3) \times 10$	m3	1.71
コンクリート金ゴテ仕上げ		$0.55 \times 0.55 \times 10$	m2	3.03
モルタル	1:3	$((0.15/2)^2 - (0.0605/2)^2) \times 3.14 \times 0.3 \times 3 \times 10$	m3	0.13
本体	R450 × 843 × 1150	10	基	10.00
床掘		$(1.81 \times 0.9 + 1.150 \times 0.388 + 0.9 \times 0.4) \times 0.41 \times 10$	m3	9.98
埋戻し		$9.984 - 3.011$	m3	6.97
残土処分		$((0.4 \times 0.4 \times 0.15 + 0.3 \times 0.3 \times 0.3) \times 3$	m3	3.01
		$+ (0.65 \times 0.65 \times 0.1 + 0.55 \times 0.55 \times 0.35) \times 10$		

種 別 健康遊具設置工
細 別 健康遊具F

(10基) 当り

略図




ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$1.2 \times 0.5 \times 10 = 6.000$	m2	6.00
型枠	均し	$(1.2 \times 0.05 \times 2 + 0.5 \times 0.05 \times 2) \times 10 = 1.700$	m2	1.70
均しコンクリート	18-8-25	$(1.2 \times 0.5 \times 0.05) \times 10 = 0.300$	m3	0.30
型枠	小型	$(1.1 \times 0.2 \times 2 + 0.4 \times 0.2 \times 2) \times 10 = 6.000$	m2	6.00
コンクリート	18-8-25	$(1.1 \times 0.4 - (0.15/2)^2 \times 3.14 \times 2) \times 0.2 \times 10 = 0.809$	m3	0.81
モルタル	1:3	$((0.15/2)^2 - (0.0605/2)^2) \times 3.14 \times 0.2 \times 2 \times 10 = 0.133$	m3	0.13
本体	2000 x 470 x 900	$10 = 10.000$	基	10.00
床掘		$(1.2 \times 0.5 \times 0.1 + 1.7 \times 1.0 \times 0.31) \times 10 = 5.870$	m3	5.87
埋戻し		$5.870 - 1.780 = 4.090$	m3	4.09
残土処分		$(1.2 \times 0.5 \times 0.15 + 1.1 \times 0.4 \times 0.2) \times 10 = 1.780$	m3	1.78


種 別 水景施設整備工
細 別 水遊び施設

(1箇所) 当り

略図





噴水部:ゴムチップ舗装A=240



種 別 水景施設整備工
細 別 水遊び施設

(1箇所) 当り



機械室: 植栽地=0


種 別		水景施設整備工				
細 別		水遊び施設			(1箇所) 当り	
種 別	規 格	計 算 式			単位	数 量
<噴水部>						
再生クラッシャーラン基礎	RC-40 t=100	$0.85 \times 0.85 \times 15 = 10.838$			m2	10.84
型枠	小型	$((0.57 \times 0.75 \times 4) + (0.42 \times 0.45 \times 4)) \times 15 = 36.990$			m2	36.99
コンクリート	18-8-25	$(0.75 \times 0.75 \times 0.57 - 0.45 \times 0.45 \times 0.42) \times 15 = 3.534$			m3	3.53
化粧蓋	噴水穴・スリット付き □450 t=30	15 = 15.000			枚	15.00
噴水ノズルユニット		15 = 15.000			基	15.00
<機械室>						
再生クラッシャーラン基礎	RC-40 t=100	$3.1 \times 2.1 = 6.510$			m2	6.51
型枠		$(0.35 \times 3.0 \times 2 + 0.35 \times 2.0 \times 2) + (0.55 \times 0.6 \times 4 + 0.4 \times 0.3 \times 4) = 5.300$			m2	5.30
コンクリート	18-8-25	$(3.0 \times 2.0 \times 0.35) + (0.6 \times 0.6 \times 0.55 - 0.3 \times 0.3 \times 0.4) - 0.3 \times 0.3 \times 0.4 = 2.226$			m3	2.23
噴水循環ポンプ	貯水タンク他共	1 = 1.000			式	1.00
グレーチング蓋	SUS 300用 □368 × T-2	1 = 1.000			枚	1.00
床掘		$(0.85 \times 0.85 \times 0.1 + 1.150 \times 1.150 \times 0.36) \times 15 + (3.1 \times 2.1 \times 0.1 + 3.6 \times 2.6 \times 0.5) = 13.556$			m3	13.56
埋戻し		$13.556 - 5.072 = 8.484$			m3	8.48
残土処分		$(0.85 \times 0.85 \times 0.1 + 0.75 \times 0.75 \times 0.36) \times 15 + (3.1 \times 2.1 \times 0.1 + 3.0 \times 2.0 \times 0.05) = 5.072$			m3	5.07

(便益施設整備工)


種 別 ベンチ工
細 別 ベンチ

(10基) 当り

略図



立面図



断面図


植栽,ダスト=(0+40)/2=20

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.4 \times 0.4 \times 2) \times 10 = 3.200$	m2	3.20
型枠	小型	$(0.3 \times 0.35 \times 4) \times 2 \times 10 = 8.400$	m2	8.40
コンクリート	18-8-25	$(0.3 \times 0.3 \times 0.35) \times 2 \times 10 = 0.630$	m3	0.63
本体		$10 = 10.000$	基	10.00
床掘		$(0.4 \times 0.4 \times 0.1 + 0.9 \times 0.9 \times 0.33) \times 2 \times 10 = 5.666$	m3	5.67
埋戻し		$5.666 - 0.914 = 4.752$	m3	4.75
残土処分		$(0.4 \times 0.4 \times 0.1 + 0.3 \times 0.3 \times 0.33) \times 2 \times 10 = 0.914$	m3	0.91

種 別 ベンチエ
細 別 縁台A

(10基) 当り

略図




カラーAsB=190

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.22*0.4*4)*10 = 3.520$	m2	3.52
モルタル	1 : 3	$(0.22*0.4*0.03*4)*10 = 0.106$	m2	0.11
本体		10 = 10.000	基	10.00
床掘		$(0.22*0.4*0.1+0.525*0.7*0.04)*4*10 = 0.940$	m3	0.94
埋戻し		$0.940-0.458 = 0.482$	m3	0.48
残土処分		$(0.22*0.4*0.13*4)*10 = 0.458$	m3	0.46

種 別 ベンチ工
細 別 縁台B


(10基) 当り

略図




平面図

座板 : 145×30 再生木材 (無垢材)
側板 : 110×20 再生木材 (無垢材)
支柱 : □60×60×3.5t A6005CS-T5
フレーム : [60×30×3.0t A6063-T5



立面図



断面図


カラーAsB=190

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.7^2 \times 3.142 / 4 + 1.1^2 \times 3.14 / 4) \times 10 = 13.347$	m2	13.35
型枠	小型	$(0.3 \times 3.142 + 1.1 \times 3.142) \times 0.1 \times 10 = 4.399$	m2	4.40
コンクリート	18-8-25	$(0.6^2 \times 3.142 / 4 + 1.0^2 \times 3.142 / 4) \times 0.1 \times 10 = 1.068$	m3	1.07
本体		10 = 10.000	基	10.00
床掘		$((0.7/2)^2 + (1.1/2)^2) \times 3.14 \times 0.01 \times 10 = 0.133$	m3	0.13
埋戻し		0 = 0.000	m3	0.00
残土処分		$((0.7/2)^2 + (1.1/2)^2) \times 3.14 \times 0.01 \times 10 = 0.133$	m3	0.13

種 別 洗い場工
細 別 手洗い場

(10基) 当り

略図




カラーAsB=190

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.82 \times 0.45 + 0.56 \times 0.56) \times 10 = 6.826$	m2	6.83
型枠	均し	$(0.05 \times 0.82 \times 2 + 0.05 \times 0.45 \times 2) \times 10 = 1.270$	m2	1.27
均しコンクリート	18-8-25	$(0.82 \times 0.45 \times 0.05) \times 10 = 0.185$	m3	0.18
エルボ	φ100	10 = 10.000	箇所	10.00
本体		10 = 10.000	基	10.00
集水桝	□460 × 700	10 = 10.000	基	10.00
床掘		$(0.56 \times 0.56 \times 0.1 + 0.82 \times 0.45 \times 0.1 + 0.66 \times 0.86 \times 0.53 + 0.97 \times 0.75 \times 0.15) \times 10 = 4.782$	m3	4.78
埋戻し		$4.782 - 2.258 = 2.524$	m3	2.52
残土処分		$(0.56 \times 0.56 \times 0.1 + 0.82 \times 0.45 \times 0.15 + 0.46 \times 0.46 \times 0.53 + 0.77 \times 0.35 \times 0.1) \times 10 = 2.258$	m3	2.26

種 別 時計台工
細 別 時計

(10基) 当り

略図



インターA=300


種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$1.0 \times 1.0 \times 10 = 10.000$	m2	10.00
型枠	小型	$1.0 \times 0.75 \times 4 \times 10 = 30.000$	m2	30.00
コンクリート	18-8-25	$1.0 \times 1.0 \times 0.75 \times 10 = 7.500$	m3	7.50
D種接地工		$10 = 10.000$	基	10.00
金コテ仕上げ		$(1.0 \times 1.0 - (0.1398/2)^2 \times 3.14) \times 10 = 9.847$	m2	9.85
本体		$10 = 10.000$	基	10.00
床掘		$(1.0 \times 1.0 \times 0.1 + 1.6 \times 1.6 \times 0.45) \times 10 = 12.520$	m3	12.52
埋戻し		$12.520 - 5.500 = 7.020$	m3	7.02
残土処分		$(1.0 \times 1.0 \times 0.1 + 1.0 \times 1.0 \times 0.45) \times 10 = 5.500$	m3	5.50

(管理施設整備工)

種 別 車止め工
細 別 車止め

(10基) 当り

略図



番号	品 名	数量	材 質	備 考
1	パイプ	1	ステンレス SUS304	φ 60. 5 × t3. 0 H. L. #240
2	差込スリーブ	2	ステンレス SUS430	φ 68 × t1. 5
3	差込スリーブ蓋	2	ステンレス SUS430	φ 76 × t2. 0
4	ロックピン	1	ステンレス SUS304	φ 12 × 99L


インターA,B=(300+300)/2=300

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=50	$(0.25 \times 0.25 \times 2) \times 10 = 1.250$	m2	1.25
型枠	小型	$(0.25 \times 0.25 \times 4 \times 2) \times 10 = 5.000$	m2	5.00
コンクリート	18-8-25	$((0.25 \times 0.25 - (0.0605/2)^2 \times 3.142) \times 0.25 \times 2) \times 10 = 0.298$	m3	0.30
本体		10 = 10.000	基	10.00
床掘		0 = 0.000	m3	0.00
埋戻し		0.000-0.000 = 0.000	m3	0.00
残土処分		0 = 0.000	m3	0.00

種 別 柵工
細 別 片開き門扉

(10基) 当り

略図




植栽地=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.45 \times 0.45) \times 2 \times 10 = 4.050$	m2	4.05
基礎ブロック	250*250*450	$2 \times 10 = 20.000$	個	20.00
モルタル	1:3	$(0.60/3 \times (0.1743^2 + 0.1743 \times 0.14 + 0.14^2) - (0.0605/2)^2 \times 3.142 \times 0.25) \times 2 \times 10 = 0.283$	m3	0.28
金ゴテ仕上げ		$(0.35 \times 0.35 - (0.0605/2)^2 \times 3.14) \times 2 \times 10 = 0.302$	m2	0.30
本体	H=1970	10	基	10.00
床掘		$(0.45 \times 0.45 \times 0.1 + 0.75 \times 0.75 \times 0.6) \times 2 \times 10 = 7.155$	m3	7.16
埋戻し		$7.155 - 1.875 = 5.280$	m3	5.28
残土処分		$(0.45 \times 0.45 \times 0.1 + 0.35 \times 0.35 \times 0.6) \times 2 \times 10 = 1.875$	m3	1.88

種 別 サイン施設工
細 別 園名板

(10基) 当り

略図




植栽,インターA=(0+300)=150

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(1.0 \times 0.5) \times 10 = 5.000$	m2	5.00
型枠	小型	$(0.4 \times 0.6 \times 4 \times 2) \times 10 = 19.200$	m2	19.20
コンクリート	18-8-25	$(0.4 \times 0.4 - (0.2/2)^2 \times 3.14) \times 0.6 \times 2 \times 10 = 1.543$	m3	1.54
ボイド	φ 200	$0.6 \times 2 \times 10 = 12.000$	m	12.00
モルタル	1:3	$(0.2/2)^2 \times 3.14 \times 0.6 \times 2 \times 10 = 0.377$	m3	0.38
本体		$10 = 10.000$	基	10.00
床掘		$(1.0 \times 0.5 \times 0.1 + 1.5 \times 1.0 \times 0.6) \times 10 = 9.500$	m3	9.50
埋戻し		$9.500 - 2.420 = 7.080$	m3	7.08
残土処分		$(1.0 \times 0.5 \times 0.1 + 0.4 \times 0.4 \times 0.6 \times 2) \times 10 = 2.420$	m3	2.42

種 別 サイン施設
細 別 総合案内板

(10基) 当り

略図




インターA=300

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.8 \times 0.8 \times 2) \times 10 = 12.800$	m2	12.80
型枠	小型	$(0.7 \times 0.8 \times 4 \times 2) \times 10 = 44.800$	m2	44.80
ポイド	φ 200	$0.8 \times 2 \times 10 = 16.000$	m	16.00
モルタル	充填 1:3	$(3.142 \times (0.2/2)^2 \times 2 - 0.14 \times 0.165) \times 0.8 \times 2 \times 10 = 0.133$	m3	0.13
コンクリート	18-8-25	$((0.7 \times 0.7 - (0.2/2)^2 \times 3.142) \times 0.8 \times 2) \times 10 = 7.337$	m3	7.34
本体		$10 = 10.000$	基	10.00
床掘		$(0.8 \times 0.8 \times 0.1 + 1.3 \times 1.3 \times 0.65) \times 2 \times 10 = 23.250$	m3	23.25
埋戻し		$23.250 - 7.650 = 15.600$	m3	15.60
残土処分		$(0.8 \times 0.8 \times 0.1 + 0.7 \times 0.7 \times 0.65) \times 2 \times 10 = 7.650$	m3	7.65

種 別 サイン施設工
細 別 制札板A

(10基) 当り

略図



側面図


植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.5 \times 0.5 \times 2) \times 10 = 5.000$	m2	5.00
型枠	小型	$(0.4 \times 0.6 \times 4 \times 2) \times 10 = 19.200$	m2	19.20
ポイド	φ 200	$0.6 \times 2 \times 10 = 12.000$	m	12.00
モルタル	充填 1:3	$(3.142 \times (0.2/2)^2 \times 0.08 \times 0.06) \times 0.6 \times 2 \times 10 = 0.319$	m3	0.32
コンクリート	18-8-25	$((0.4 \times 0.4 - (0.2/2)^2 \times 3.142) \times 0.6 \times 2) \times 10 = 1.543$	m3	1.54
本体		$10 = 10.000$	基	10.00
床掘		$(0.5 \times 0.5 \times 0.1 \times 2 + 1.98 \times 1.0 \times 0.75) \times 10 = 15.350$	m3	15.35
埋戻し		$15.350 - 2.420 = 12.930$	m3	12.93
残土処分		$((0.5 \times 0.5 \times 0.1 + 0.4 \times 0.4 \times 0.6) \times 2) \times 10 = 2.420$	m3	2.42


種 別 サイン施設工
細 別 制札板B

(10基) 当り

略図



側面図




ダスト=40

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.5 \times 0.5 \times 2) \times 10 = 5.000$	m2	5.00
型枠	小型	$(0.4 \times 0.6 \times 4 \times 2) \times 10 = 19.200$	m2	19.20
ボイド	φ 200	$0.6 \times 2 \times 10 = 12.000$	m	12.00
モルタル	充填 1:3	$(3.142 \times (0.2/2)^2 - 0.08 \times 0.06) \times 0.6 \times 2 \times 10 = 0.319$	m3	0.32
コンクリート	18-8-25	$((0.4 \times 0.4 - (0.2/2)^2 \times 3.142) \times 0.6 \times 2) \times 10 = 1.543$	m3	1.54
本体		$10 = 10.000$	基	10.00
床掘		$(0.5 \times 0.5 \times 0.1 \times 2 + 1.68 \times 1.0 \times 0.60) \times 10 = 10.580$	m3	10.58
埋戻し		$10.580 - 2.420 = 8.160$	m3	8.16
残土処分		$((0.5 \times 0.5 \times 0.1 + 0.4 \times 0.4 \times 0.6) \times 2) \times 10 = 2.420$	m3	2.42

種 別 サイン施設工
細 別 駐車場案内板

(10基) 当り

略図




植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.5 \times 0.5 \times 2) \times 10 = 5.000$	m2	5.00
型枠	小型	$(0.4 \times 0.5 \times 4 \times 2) \times 10 = 16.000$	m2	16.00
コンクリート	18-8-25	$(0.4 \times 0.4 - (0.08/2)^2 \times 3.142) \times 0.5 \times 2 \times 10 = 1.550$	m3	1.55
本体		10 = 10.000	基	10.00
床掘		$(0.5 \times 0.5 \times 0.1 \times 2 + 1.6 \times 1.0 \times 0.5) \times 10 = 8.500$	m3	8.50
埋戻し		$8.500 - 2.100 = 6.400$	m3	6.40
残土処分		$((0.5 \times 0.5 \times 0.1 + 0.4 \times 0.4 \times 0.5) \times 2) \times 10 = 2.100$	m3	2.10

種 別 サイン施設工
細 別 駐輪場案内板

(10基) 当り

略図




植栽=0

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$0.4 \times 0.4 \times 10 = 1.600$	m2	1.60
型枠	小型	$(0.3 \times 0.5 \times 4) \times 10 = 6.000$	m2	6.00
コンクリート	18-8-25	$((0.3 \times 0.3 - (0.08/2)^2 \times 3.142) \times 0.5) \times 10 = 0.425$	m3	0.42
本体		$10 = 10.000$	基	10.00
床掘		$(0.4 \times 0.4 \times 0.1 + 0.9 \times 0.9 \times 0.5) \times 10 = 4.210$	m3	4.21
埋戻し		$4.210 - 0.610 = 3.600$	m3	3.60
残土処分		$(0.4 \times 0.4 \times 0.1 + 0.3 \times 0.3 \times 0.5) \times 10 = 0.610$	m3	0.61

種 別 サイン施設工
細 別 防災サイン

(10基) 当り

略図




インターA=300

[illegible]

種 別 サイン施設工
細 別 記念碑①再設置

(10基) 当り

略図




植栽=0

種 別	規 格	計 算 式	単位	数 量
本体	再設置	10 = 10.000	基	10.00
床掘		$(0.7 \times 0.4 \times 0.1 + 0.9 \times 0.6 \times 0.05) \times 10 = 0.550$	m3	0.55
埋戻し		$0.550 - 0.370 = 0.180$	m3	0.18
残土処分		$(0.7 \times 0.4 \times 0.1 + 0.6 \times 0.3 \times 0.05) \times 10 = 0.370$	m3	0.37

種 別 サイン施設工
細 別 記念碑②再設置

(10基) 当り

略図







植栽=0

種 別	規 格	計 算 式	単位	数 量
本体	再設置	10 = 10.000	基	10.00
床掘		$(0.5 \times 0.5 \times 0.1 + 0.7 \times 0.7 \times 0.05) \times 10 = 0.495$	m3	0.50
埋戻し		$0.495 - 0.330 = 0.165$	m3	0.17
残土処分		$(0.5 \times 0.5 \times 0.1 + 0.4 \times 0.4 \times 0.05) \times 10 = 0.330$	m3	0.33

種 別 防災施設工
細 別 防災井戸

(1箇所) 当り

略図






種 別		防災施設工			
細 別		防災井戸			
		(1箇所) 当り			
種 別	規 格	計 算 式		単位	数 量
<ポンプ本体>					
再生クラッシャーラン基礎	RC-40 t=100	$0.7 \times 0.7 = 0.490$		m2	0.49
型枠	小型	$0.15 \times 0.6 \times 4 + 1.0 \times 0.5 \times 4 = 2.360$		m2	2.36
コンクリート	18-8-25	$(0.6 \times 0.6 - (0.1/2)^2 \times 3.14) \times 0.15 + (0.5 \times 0.5 - (0.162/2)^2 \times 3.142) \times 1 = 0.282$		m3	0.28
ポンプ本体		1 = 1.000		基	1.00
<集水桝>					
再生クラッシャーラン基礎	RC-40 t=100	$0.56 \times 0.56 = 0.314$		m2	0.31
モルタル	1:3	$0.56 \times 0.56 \times 0.03 = 0.009$		m3	0.01
エルボ	φ100	1 = 1.000		箇所	1.00
縁塊 □360用	クサリ付	1 = 1.000		個	1.00
側塊 □360用	h=300	3 = 3.000		個	3.00
側塊 □360用	h=150	1 = 1.000		個	1.00
底塊 □360用		1 = 1.000		個	1.00
グレーチング蓋(受枠共)	430×430×t50 T-2	1 = 1.000		枚	1.00
床掘		$0.7 \times 0.7 \times 0.1 + 0.85 \times 1.1 \times 0.32 + 0.56 \times 0.56 \times 0.1 + 0.86 \times 0.71 \times 0.66 = 0.783$		m3	0.78
埋戻し		$0.783 - 0.326 = 0.457$		m3	0.46
残土処分		$0.7 \times 0.7 \times 0.1 + 0.6 \times 0.6 \times 0.15 + 0.5 \times 0.5 \times 0.17 + 0.56 \times 0.56 \times 0.13 + 0.46 \times 0.46 \times 0.1 = 0.326$		m3	0.33

(建築施設組立設置工)

種 別 便所工
細 別 トイレ

(1基) 当り

略図



配筋重量表

符号	径	長さ	本数	単位重量	1本当り重量	重量	1基当り
S1	D10	6000	30	0.560	3.360	100.80	摘要
S2	D10	1620	15	0.560	0.907	13.61	
S3	D10	6000	30	0.560	3.360	100.80	
S4	D10	1620	15	0.560	0.907	13.61	
S5	D10	2785	70	0.560	1.560	109.20	
S6	D10	2785	70	0.560	1.560	109.20	
S7	D10	3157	8	0.560	1.768	14.14	
S8	D10	1602	22	0.560	0.897	19.73	
P1	D10	1026	111	0.560	0.575	63.83	
P2-1	D10	6000	12	0.560	3.360	40.32	
P2-2	D10	1570	6	0.560	0.879	5.27	
P2-3	D10	3597	6	0.560	2.014	12.08	
P3	D10	3097	16	0.560	1.734	27.74	
合計						630.33Kg	

折り曲げ内法直径
D10×3d=30


インター-A=300

[illegible]

[illegible]

種 別 あずまや工
細 別 あずまやA

(10基) 当り



カラーAsB=190


種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=150	$(0.9 \times 0.9) \times 4 \times 10 = 32.400$	m2	32.40
型枠	均し	$(0.05 \times 0.9 \times 4) \times 4 \times 10 = 7.200$	m2	7.20
均しコンクリート	18-8-25	$(0.9 \times 0.9 \times 0.05) \times 4 \times 10 = 1.620$	m3	1.62
型枠	小型	$(0.6 \times 0.8 \times 4) \times 4 \times 10 = 76.800$	m2	76.80
コンクリート	18-8-25	$((0.8 \times 0.8 \times 0.6 - (0.1652/2)^2 \times 3.142 \times 0.35) \times 4) \times 10 = 15.060$	m3	15.06
アンカーボルト	M12×200L	$4 \times 4 \times 10 = 160.000$	本	160.00
鉄筋	D13	$(0.7 \times 8) \times 4 \times 10 = 224.000$	m	
		$224.000\text{m} \times 0.995\text{kg/m} = 222.88\text{kg} / 1000 = 0.223\text{t}$	t	0.22
本体	□3000	$10 = 10.000$	基	10.00

[illegible]


種 別 あずまや工
細 別 あずまやB

(10基) 当り

略図



平面図





カラーAsB=190

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=150	$((0.9 \times 0.9) \times 4) \times 10 = 32.400$	m2	32.40
型枠	小型	$((0.8 \times 0.8 \times 4) \times 4) \times 10 = 102.400$	m2	102.40
コンクリート	18-8-25	$((0.8 \times 0.8 \times 0.8) \times 4) \times 10 = 20.480$	m3	20.48
アンカーボルト	M16 × 600L	$4 \times 4 \times 10 = 160.000$	本	160.00
防災四阿本体	□3000	$10 = 10.000$	基	10.00
床掘		$((0.9 \times 0.9 \times 0.15 + 1.4 \times 1.4 \times 0.88) \times 4) \times 10 = 73.852$	m3	73.85
埋戻し		$73.852 - 25.392 = 48.460$	m3	48.46
残土処分		$(0.9 \times 0.9 \times 0.15 + 0.8 \times 0.8 \times 0.8 + 0.12 \times 0.12 \times 0.09) \times 4 \times 10 = 25.392$	m3	25.39

種	別	あずまや工
細	別	あずまやC

(10基) 当り



立断面図

鉄筋重量表

(基礎1ヶ所当り)

[illegible]

合計	18.51	kg
----	-------	----

インター-A=300

種 別	規 格	計 算 式	単位	数 量
再生クラッシャーラン基礎	RC-40 t=100	$(0.4*0.4*6+1.0*1.0)*10$	m2	19.60
型枠	均し	$(0.05*1.0*4)*10$	m2	2.00
均しコンクリート	18-8-25	$(1.0*1.0*0.05)*10$	m3	0.50
型枠	小型	$((0.3*0.3*4)*6+(0.45*0.9*4))*10$	m2	37.80
コンクリート	18-8-25	$((0.3*0.3*0.3)*6+(0.9*0.9*0.45))*10$	m3	5.27
鉄筋	D10	上記鉄筋重量表より18.51kg	t	0.10
アンカーボルト	M16	$4*10$	本	40.00
本体	φ2880	10	基	10.00
床掘		$((0.4*0.4*0.1)*6+(1.0*1.0*0.1+1.5*1.5*0.4))*10$	m3	10.96
埋戻し		10.960-5.295	m3	5.67
残土処分		$((0.4*0.4*0.1)*6+1.0*1.0*0.15+0.9*0.9*0.35)*10$	m3	5.30