

市道久喜7053号線（久喜工業高校東側）他舗装本復旧工事

久喜市 古久喜他 地内

数 量 計 算 書

数量総括表

工種	種別	細別	単位	路線名			合計	合計
				7053号線	7052号線	7375号線		
撤去工	舗装版破碎	バックホウ山積0.28m ³	m ²	536.24	534.26	66.28	1,136.78	1,140.00
	As廃材処理	4tダンプ・L=5.0km	m ³	26.81	26.71	3.31	56.83	60.00
	As切断	厚 15cmまで	m	9.87	3.25	6.40	19.52	20.00
	切断濁水量	2t積トラック・L=10.0kmまで	m ³	0.013	0.004	0.008	0.025	0.025
舗装工	不陸整正	再生粒調碎石 補足材 1cm	m ²	536.24	534.26	66.28	1,136.78	1,140.00
	表層(1.4≦W≦3.0)	再生密粒度As 厚5cm PK-3	m ²	536.24	534.26	66.28	1,136.78	1,140.00
区画線工	区画線	黄色・文字、記号・幅15cm換算	m	3.40			3.4	3.0
	区画線	赤色・10m ² 未満	m ²		4.64		4.6	5.0
	区画線	白色・破線・幅45cm	m		1.44		1.4	1.0
	区画線	白色・ゼブラ・幅45cm	m	1.40			1.4	1.0
	区画線	文字、記号・幅15cm換算	m		30.8		30.8	31.0
仮設工	交通誘導警備員	交通誘導警備員B	式	1.000	1.000	1.000	1.000	1.000

数量計算書

市道久喜7053号線

(1.4 ≤ W ≤ 3.0)

面積計算書

不陸整正・表層

市道久喜7053号線

測 点	距 離(m)	幅(m)	平均幅(m)	面積(m ²)
No.0		5.05		
No.0 + 1.16	1.16	3.05	4.05	4.70
No.1	18.84	2.93	2.99	56.33
No.2	20.00	3.01	2.97	59.40
No.2 + 5.90	5.90	3.07	3.04	17.94
No.2 + 5.90	0.00	3.55	3.31	0.00
No.3	14.10	3.90	3.73	52.59
No.4	20.00	3.89	3.90	78.00
No.5	20.00	3.93	3.91	78.20
No.5 + 9.70	9.70	3.30	3.62	35.11
No.5 + 9.70	0.00	3.55	3.43	0.00
No.6	10.30	3.56	3.56	36.67
No.7	20.00	2.97	3.27	65.40
No.7 + 14.90	14.90	2.93	2.95	43.96
合 計	154.90			528.30

舗装版破碎
不陸整正・表層

数 量 計 算 書

市道久喜7053号線

①	(5.67 + 3.67) × 1.7 ÷ 2	7.94 m ²
合 計		7.94 m ²

数量計算書

市道久喜7052号線

[illegible]

面積計算書

市道久喜7052号線

測 点	距 離 (m)	幅 (m)	平均幅 (m)	面積 (m2)
No.0		5.83		
No.0 + 1.81	1.81	2.78	4.31	7.80
No.1	18.19	2.59	2.69	48.93
No.2	20.00	2.75	2.67	53.40
No.2 + 6.75	6.75	2.85	2.80	18.90
No.3	13.25	2.76	2.81	37.23
No.4	20.00	2.75	2.76	55.20
No.4 + 0.55	0.55	2.87	2.81	1.55
No.5	19.45	2.81	2.84	55.24
No.6	20.00	2.80	2.81	56.20
No.7	20.00	2.81	2.81	56.20
No.8	20.00	2.83	2.82	56.40
No.9	20.00	2.79	2.81	56.20
No.9 + 5.03	5.03	2.76	2.78	13.98
合 計	185.03			517.23

舗装版破碎 不陸整正・表層			数量計算書	市道久喜7052号線
①	$5.64 \times 0.47 \div 2$	1.33 m ²		
②	$5.64 \times 0.56 \div 2$	1.58 m ²		
③	$6.24 \times 4.88 \div 2$	15.23 m ²		
合計		18.14 m ²		

控除面積			数量計算書	市道久喜7052号線
人孔①	1.06×1.05	1.11		
合計		1.11 m ²		

数量計算書

市道久喜7375号線

面積計算書

市道久喜7375号線①

[illegible]

面積計算書

市道久喜7375号線②

測 点	距 離(m)	幅(m)	平均幅(m)	面積(m ²)
No.0		6.77		
	1.72		4.79	8.24
No.0 + 1.72		2.81		
	8.84		2.90	25.64
No.0 + 10.56		2.99		
	1.24		1.50	1.86
No.0 + 11.8		0.00		
合 計	11.80			35.74

数量計算書			市道久喜7375号線
控除面積			
人孔②	1.06×1.03	1.09	
集水枥①	0.14×0.9	0.13	
集水枥②	0.14×0.9	0.13	
合 計		1.35 m ²	