

延長集計表

図面 番 号	处 理 分 区	施 設 番 号	管 径 (mm)	延 長 (m)	φ 150 (mm)	φ 200 (mm)	φ 250 (mm)	φ 300 (mm)	φ 350 (mm)	φ 400 (mm)	φ 450 (mm)	φ 500 (mm)	φ 600 (mm)	φ 700 (mm)	φ 800 (mm)	φ 900 (mm)	φ 1,000 (mm)	φ 1,100 (mm)	φ 1,200 (mm)	φ 1,350 (mm)	φ 1,500 (mm)	φ 1,650 (mm)	φ 1,800 (mm)	φ 2,000 (mm)	φ 3,000 (mm)
1/7	南部12	209	250	25.62			25.62																		
1/7	南部12	202-2①	250	47.12			47.12																		
1/7	南部12	202-2②	250	46.23			46.23																		
1/7	南部12	202-2③	250	38.20			38.20																		
1/7	南部12	207	250	40.00			40.00																		
1/7	南部12	206①	250	14.43			14.43																		
1/7	南部12	206②	250	14.32			14.32																		
1/7	南部12	206③	250	17.98			17.98																		
1/7	南部12	205-1	250	41.31			41.31																		
1/7	南部12	205-2①	250	26.97			26.97																		
1/7	南部12	205-2②	250	26.20			26.20																		
1/7	南部12	204①	250	37.20			37.20																		
1/7	南部12	204②	250	37.69			37.69																		
1/7	南部12	203	250	50.15			50.15																		
1/7	南部12	202-1①	250	29.40			29.40																		
1/7	南部12	220①	250	49.60			49.60																		
1/7	南部12	218-1①	250	19.70			19.70																		
1/7	南部12	218-1②	250	8.20			8.20																		
1/7	南部12	218-1③	250	33.00			33.00																		
1/7	南部12	218-1④	250	5.50			5.50																		
1/7	南部12	218-1⑤	250	6.10			6.10																		
1/7	南部12	218-16	250	4.80			4.80																		
1/7	南部12	218①	250	29.50			29.50																		
1/7	南部12	41①	250	36.90			36.90																		
2/7	南部12	202-1②	250	29.40			29.40																		
2/7	南部12	202-1③	250	8.95			8.95																		
2/7	南部12	S9-2①	150	8.95	8.95																				
2/7	南部12	S9-2②	200	11.50		11.50																			
2/7	南部12	S9-1①	250	7.85			7.85																		
2/7	南部12	S9-1②	250	31.05			31.05																		
2/7	南部12	214	250	39.60			39.60																		
2/7	南部12	215①	250	42.06			42.06																		
2/7	南部12	217①	250	5.00			5.00																		
2/7	南部12	217②	250	18.45			18.45																		
2/7	南部12	217③	250	43.55			43.55																		
2/7	南部12	217④	250	7.90			7.90																		
2/7	南部12	218②	250	25.50			25.50																		
2/7	南部12	219①	250	30.45			30.45																		
2/7	南部12	219②	250	29.68			29.68																		
2/7	南部12	220②	250	33.21			33.21																		
2/7	南部12	221①	250	8.30			8.30																		
2/7	南部12	217-1①	250	20.20			20.20																		
2/7	南部12	217-1②	250	42.70			42.70																		
2/7	南部12	219-1①	250	48.80			48.80																		
2/7	南部12	219-1②	250	7.26			7.26																		
2/7	南部12	221②	250	47.30			47.30																		
2/7	南部12	221③	250	5.67			5.67																		
2/7	南部12	222-1①	150	8.97	8.97																				
2/7	南部12	222-1②	150	8.24	8.24																				
2/7	南部12	222-1③	150	8.33	8.33																				
2/7	南部12	222-1④	150	4.00	4.00																				
2/7	南部12	222-2①	250	8.26			8.26																		
2/7	南部12	222-2②	250	22.48			22.48																		
2/7	南部12	222-2③	250	2.68			2.68																		
2/7	南部12	222-2④	250	19.20			19.20																		

延長集計表

[illegible]

延長集計表

[illegible]

延長集計表

[illegible]

延長集計表

[illegible]

延長集計表

[illegible]

管 路 清 掃 工

	内 径 (mm)	土砂深率 (%)	延 長 (m)	標準作業量 (m/日)	閉塞断面積 ($\times 10^{-2} \text{m}^2$)	清掃土砂量 ($\text{m}^3/\text{日}$)	土 砂 量 (m^3)	清掃日数 (日)
高圧洗浄車	150	5	38.49	693	0.033	0.229	0.013	0.060
	200	5	124.81	693	0.059	0.409	0.074	0.180
	250	5	7,491.02	693	0.092	0.638	6.892	10.810
	300	5	0.00	673	0.132	0.889	0.000	0.000
	350	5	0.00	622	0.180	1.120	0.000	0.000
	400	5	0.00	563	0.235	1.324	0.000	0.000
	450	5	786.20	493	0.297	1.465	2.335	1.590
	500	5	0.00	470	0.367	1.725	0.000	0.000
	600	5	0.00	334	0.529	1.767	0.000	0.000
	700	5	0.00	226	0.719	1.625	0.000	0.000
小計	—	—	8,440.52	—	—	—	9.314	12.640
強力吸引車	800	5	0.00	671	0.940	6.308	0.000	0.000
	900	5	0.00	543	1.189	6.457	0.000	0.000
	1,000	5	0.00	453	1.468	6.651	0.000	0.000
	1,100	5	0.00	386	1.776	6.856	0.000	0.000
	1,200	5	0.00	336	2.114	7.104	0.000	0.000
	1,350	5	0.00	281	2.676	7.520	0.000	0.000
	1,500	5	0.00	273	3.303	9.018	0.000	0.000
	1,650	5	0.00	225	3.997	8.994	0.000	0.000
	1,800	5	0.00	189	4.757	8.991	0.000	0.000
	2,000	5	0.00	153	5.873	8.986	0.000	0.000
小計	—	—	0.00	—	—	—	0.000	0.000
	800	5	0.00	671	0.940	6.308	0.000	0.000
	900	5	0.00	543	1.189	6.457	0.000	0.000
	1,000	5	0.00	453	1.468	6.651	0.000	0.000
	1,100	5	0.00	386	1.776	6.856	0.000	0.000
	1,200	5	0.00	336	2.114	7.104	0.000	0.000
	1,350	5	0.00	281	2.676	7.520	0.000	0.000
	1,500	5	0.00	273	3.303	9.018	0.000	0.000
	1,650	5	0.00	225	3.997	8.994	0.000	0.000
	1,800	5	0.00	189	4.757	8.991	0.000	0.000
	2,000	5	0.00	153	5.873	8.986	0.000	0.000
小計	—	—	0.00	—	—	—	0.000	0.000
合 計	—	—	8,440.52	—	—	—	9.314	12.64

※ 1日当りの清掃土砂量 = (標準作業量) $\times$ (閉塞断面積)

処分土砂量(m^3)

6.986

搬入汚泥量(t)

7.684

戸田市