

数 量 総 括 表 (林 道 小 川 線 道 路 維 持 工 事)

工 種	仕 様 ・ 寸 法	計 算 式	数 量	単位	備 考
土工					工事延長 L= 48.7 m
作業土工					
床掘り(掘削)		数量計算書より = 55.4	55	m3	
残土運搬処理	運搬距離 L=1.0km	13.3 = 13.3	13	m3	
残土運搬処理	運搬距離 L=2.5km	$55.4 - 33.6 / 0.9 - 13.3 / 0.9 = 3.3$	3	m3	
路肩盛土		数量計算書より = 13.3	13	m3	
埋戻し		数量計算書より = 33.6	34	m3	
舗装工					
アスファルト舗装工					
舗装版切断	As+Co	t=150mm $1.8 + 8.0 + 2.5 + 1.25 + 20.2 + 1.25 = 35.0$	35	m	
舗装版取壊し	As+Co	t=150mm 数量計算書より = 42.4	42	m2	
殻運搬	As殻	$42.4 * 0.05 = 2.12$	2	m3	片道運搬距離 L= 20.7 km
殻運搬	Co殻	無筋 $42.4 * 0.1 = 4.24$	4	m3	片道運搬距離 L= 20.7 km
殻処分	As殻	$= 2.12$	2	m3	$2.12 \times 2.35 = 4.98$ t
殻処分	Co殻	無筋 $= 4.24$	4	m3	$4.24 \times 2.35 = 9.96$ t
下層路盤	再生碎石(RC-40)	t=150mm 数量計算書より = 33.5	34	m2	
上層路盤	鉄鋼スラグ(RM-30)	t=100mm 数量計算書より = 40.6	41	m2	

数 量 総 括 表 (林 道 小 川 線 道 路 維 持 工 事)

[illegible]

数量計算書(林道小川線 道路維持工
事)

測 点		測点間距離	床 掘 (掘 削)			埋 戻 し			盛 土			舗 装 版 取 壊		
			面積	平均面積	体積	面積	平均面積	体積	面積	平均面積	体積	幅員	平均幅員	面積
自														
至	1 工区													
自	No. 0	5.000	2.87			1.61								
至	No. 0+5.0		2.87	2.87	14.4	1.61	1.61	8.1						17.2
自	No. 0+5.0	3.000	0.25			0.00								
至	No. 0+8.0		0.25	0.25	0.8	0.00	0.00	0.0						
自														
至														
自														
至	2 工区													
自	No. 0'	20.200	1.99			1.26								
至	No. 1' +0.2		1.99	1.99	40.2	1.26	1.26	25.5						25.2
自														
至														
自														
至	3 工区													
自	No. 0' ' +1.5	7.500							0.67					
至	No. 0' '' +9.0		1.04	0.86	6.5									
自	No. 0' '' +9.0	13.000							1.04					
至	No. 1' '' +2		0.00	0.52	6.8									
自														
至														
自														
至														
自														
至														
自														
至														
自														
至														
自														
至														
自														
至														
自														
至														
自														
至														
合 計	48.700			55.4			33.6			13.3			42.4	

数量計算書(林道小川線 道路維持工事)

測点	測点間距離	表層 施工幅 W = 1.4m 未滿			表層 施工幅 W=1.4m 以上 3.0m 未滿			上層路盤			下層路盤		
		幅員	平均幅員	面積	幅員	平均幅員	面積	幅員	平均幅員	面積	幅員	平均幅員	面積
自													
至	1 工区												
自	No. 0										1.44		
至	No. 0+5.0	5.000					15.4			15.4	1.88	1.66	8.3
自	No. 0+5.0												
至	No. 0+8.0	3.000											
自													
至													
自													
至	2 工区												
自	No. 0'												
至	No. 1' +0.2	20.200		25.2						25.2			25.2
自													
至													
自													
至	3 工区												
自	No. 0' ' +1.5												
至	No. 0' ' +9.0	7.500											
自	No. 0' ' +9.0												
至	No. 1' ' +2	13.000											
自													
至													
自													
至													
自													
至													
自													
至													
自													
至													
自													
至													
自													
至													
自													
至													
自													
至													
合 計	48.700			25.2			15.4			40.6			33.5