

坂戸都市計画事業片柳土地区画整理事業
区画街路 6 - 7 2 号線外 2 路線
街 路 築 造 等 工 事

数 量 計 算 書

令和 8 年 度

工事名：片柳土地区画整理事業 区画街路6-72号線外2路線街路築造等工事

全体数量総括表

工事区分 (LEVEL1)	工 種 (LEVEL2)	種 別 (LEVEL3)	細 別 (LEVEL4)	規 格 (LEVEL5)	単位	設計数量			合計	積算数量	摘 要
						区6-72号線	区6-73号線	区6-4号線			
工事延長											
					m	49.85	24.81	19.28	93.94		
道路改良	道路土工	掘削工	掘削	土砂, オブ・ンカット, 無し, 無し, 5,000m3未満	m3	214.22	94.94	46.14	355.30	360	
		盛土工	盛土 (路肩盛土)	発生土 2.5m未満	m3	-	-	3.42	3.42	3	
				BH0. 2m³ (小規模)	m3	13.88	6.58	3.42	23.88	20	
		残土処理工	土砂等運搬	BH0. 8m3 DID無し L=7.5km以下	m3	200.29	87.63	38.54	326.46	330	
		路床置換工	路床置換	RC-40, t=50cm 4.0m以上 1000m3未満 障害無し	m3	126.79	62.48	47.43	236.70	240	
	舗装工	アスファルト舗装工	上層路盤 (車道・路肩部)	M-30, 厚6cm 幅3.0m以上	m2	253.50	124.94	94.85	473.29	473	
				M-30, 厚1.5cm 幅3.0m以上	m2	4.68	-	-	4.68	5	
			表層 (車道・路肩部)	再生密粒度As (13), 厚4cm, 幅3.0m以上	m2	255.72	124.94	101.73	482.39	482	
			不陸整正	M-30, 補足材厚さ1mm以上6mm未満	m2	-	-	6.88	6.88	7	
	排水構造物工	側溝工	長尺U形側溝	300×300	m	88.86	51.36	38.28	178.50	179	
			泉蓋設置	B型配列 (普通型)	枚	56	32	24	112	112	
				B型配列 (普通型手掛付)	枚	18	10	8	36	36	
				B型配列 (網付)	枚	74	43	32	149	149	
		函渠工	横断暗渠	400×250	m	8.82	-	-	8.82	9	
		集水樹工	プレキャスト集水樹	B型 500×500×650	基	4	-	-	4	4	
		作業土工	床掘	BH0. 2m³ (小規模)	m3	1.55	-	-	1.55	2	
			埋戻	BH0. 2m³ (小規模)	m3	0.05	-	-	0.05	0.05	

工事名：片柳土地区画整理事業 区画街路6-72号線外2路線街路築造等工事

全 体 数 量 総 括 表										
工事区分 (LEVEL1)	工 種 (LEVEL2)	種 別 (LEVEL3)	細 別 (LEVEL4)	規 格 (LEVEL5)	単位	設計数量		合計	積算数量	摘 要
						区6-72号線	区6-73号線	区6-4号線		
			基面整正		m2	52.43	30.30	22.59	105.32	105
	付帯工	構造物撤去工	仮排水管撤去		m	9.80	-	-	9.80	10
			仮排水管処分		m3	0.05	-	-	0.05	0.05
		擦付け舗装	上層路盤	RM-40, 平均厚17cm	m2	-	-	38.89	38.89	39
			表層	再生密粒度As(13), 厚4cm, 幅3.0m以上	m2	-	-	38.89	38.89	39
	汚水排水工	路縁延長			m	48.24	28.00	20.00	96.24	96
		管渠延長			m	47.34	27.55	20.00	94.89	95
		基礎延長		砂基礎	m	47.20	27.48	20.00	94.68	95
		管路土工	機械掘削	BH0. 20m3	m3	65.11	17.91	14.43	97.45	100
			埋戻	BH0. 20m3 再生砂	m3	59.23	14.58	12.05	85.86	90
			残土等処分		m3	65.11	17.91	14.43	97.45	100
		管基礎工		砂基礎	m3	4.01	2.25	1.64	7.90	8
		マンホール工	組立マンホール設置	1号 人孔深2.0m以下	箇所	1			1	1
			底部工	1号	箇所	1			1	1
			蓋及び口環	T-14	組	1			1	1
			底版	有効高130	個	1			1	1
			管取付壁	900×1200	個	1			1	1

坂戸都市計画事業片柳土地区画整理事業
区画街路 6 - 7 2 号線外 2 路線
街 路 築 造 等 工 事

数 量 計 算 書
区6-72号線

令和 8 年 度

[illegible]

1. 道 路 土 工

土 工 数 量 調 書

掘削

V = 道路掘削

= 214.22

= 214.22 m³

埋戻

V = 道路埋戻

= 13.88

= 13.88 m³

土砂等運搬

V = 道路掘削(土砂)+排水構造物残土-埋戻/0.9

= 214.22 + 1.49 - 13.88 / 0.9

= 200.29 m³


掘削工

[illegible]


路床置換工計算書								
路床置換工(RC-40)								
測点	距離 (m)	幅員 (m)	平均幅員 (m)	面積 (m2)	置換厚 (m)	平均厚 (m)	体積 (m3)	摘 要
No. 1 + 11.256		4.92			0.500			
	8.744		4.92	43.02		0.50	21.51	
No. 2		4.92			0.500			
	6.456		4.92	31.76		0.50	15.88	
No. 2 + 6.456		4.92			0.500			
	0.351		4.92	1.73		0.50	0.87	
No. 2 + 6.807		4.92			0.500			
不定形1				2.86		0.50	1.43	車道舗装数量調査参照
No. 2 + 7.357		5.46			0.500			
	1.240		5.46	6.77		0.50	3.39	
No. 2 + 8.597		5.46			0.500			
	2.903		5.46	15.85		0.50	7.93	
No. 2 + 11.500		5.46			0.500			
	3.099		5.46	16.92		0.50	8.46	
No. 2 + 14.599		5.46			0.500			
	1.433		5.46	7.82		0.50	3.91	
No. 2 + 16.032		5.46			0.500			
不定形2				0.59		0.50	0.30	車道舗装数量調査参照
不定形3				0.59		0.50	0.30	車道舗装数量調査参照
No. 2 + 16.832		4.92			0.500			
	3.168		4.92	15.59		0.50	7.80	
No. 3		4.92			0.500			
	5.000		4.92	24.60		0.50	12.30	
No. 3 + 5.000		4.92			0.500			
	12.952		4.92	63.72		0.50	31.86	
No. 3 + 17.952		4.92			0.500			
不定形4				1.85		0.50	0.93	車道舗装数量調査参照
不定形5				19.83		0.50	9.92	車道舗装数量調査参照
合計							126.79	

2. 鋪 装 工

車道舗装数量調書




(不定形1) (不定形2) (不定形3)




符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.920	0.551	-	-	2.711
2	5.480	0.551	-	-	3.008
倍面積 (m ²)					5.719
面積 (m ²)					2.860

符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.400	0.135	-	-	0.594
2	4.400	0.135	-	-	0.594
倍面積 (m ²)					1.188
面積 (m ²)					0.594





符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.400	0.135	-	-	0.594
2	4.400	0.135	-	-	0.594
倍面積 (m ²)					1.188
面積 (m ²)					0.594



符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.660	0.506	-	-	2.358
2	0.506	0.231	-	-	0.131
3	4.425	0.117	-	-	0.594
4	4.425	0.117	-	-	0.518
倍面積 (m ²)					3.609
面積 (m ²)					1.849



符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.443	0.148	-	-	0.658
2	4.443	0.109	-	-	0.484
3	4.669	0.237	-	-	1.107
4	0.341	0.027	-	-	0.009
5	7.402	1.636	-	-	12.110
6	0.328	0.054	-	-	0.018
7	7.596	0.261	-	-	1.983
8	9.574	2.432	-	-	23.284
倍面積 (m ²)					39.653
面積 (m ²)					19.827



符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.400	0.530	-	-	2.332
2	4.400	0.530	-	-	2.332
倍面積 (m ²)					4.664
面積 (m ²)					2.332

符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.512	0.520	-	-	2.346
2	4.512	0.520	-	-	2.346
倍面積 (m ²)					4.692
面積 (m ²)					2.346

上層路盤(車道部) 舗 装 工 計 算 書					
測 点	距 離 (m)	幅 員 (m)	平均幅員 (m)	面 積 (m ²)	摘 要
No. 1 + 11.256		4.92			道路幅6.0m－ U形側溝0.54m －U形側溝0.54m
	8.744		4.92	43.02	
No. 2		4.92			
	6.456		4.92	31.76	
No. 2 + 6.456		4.92			
	0.351		4.92	1.73	
No. 2 + 6.807		4.92			
不定形1				2.86	
No. 2 + 7.357		5.46			道路幅6.0m－ U形側溝0.54m
	1.240		5.46	6.77	
No. 2 + 8.597		5.46			
	2.903		5.46	15.85	
No. 2 + 11.500		5.46			
	3.099		5.46	16.92	
No. 2 + 14.599		5.46			
	1.433		5.46	7.82	
No. 2 + 16.032		5.46			
不定形2				0.59	
不定形3				0.59	
No. 2 + 16.832		4.92			道路幅6.0m－ U形側溝0.54m －U形側溝0.54m
	3.168		4.92	15.59	
No. 3		4.92			
	5.000		4.92	24.60	
No. 3 + 5.000		4.92			
	12.952		4.92	63.72	
No. 3 + 17.952		4.92			
不定形4				1.85	
不定形5				19.83	
合計				253.50	

舗 装 工 計 算 書					
表層(車道部)					
測 点	距離 (m)	幅員 (m)	平均幅員 (m)	面積 (m ²)	摘 要
No. 1 + 11.756		4.92			道路幅6.0m－ U形側溝0.54m －U形側溝0.54m
	8.244		4.92	40.56	
No. 2		4.92			
	6.456		4.92	31.76	
No. 2 + 6.456		4.92			
	0.351		4.92	1.73	
No. 2 + 6.807		4.92			
不定形1				2.86	
No. 2 + 7.357		5.46			道路幅6.0m－ U形側溝0.54m
	1.240		5.46	6.77	
No. 2 + 8.597		5.46			
	2.903		5.46	15.85	
No. 2 + 11.500		5.46			
	3.099		5.46	16.92	
No. 2 + 14.599		5.46			
	1.433		5.46	7.82	
No. 2 + 16.032		5.46			
不定形2				0.59	
不定形3				0.59	
					道路幅6.0m－ U形側溝0.54m －U形側溝0.54m
No. 2 + 16.832		4.92			
	3.168		4.92	15.59	
No. 3		4.92			
	5.000		4.92	24.60	
No. 3 + 5.000		4.92			
	12.952		4.92	63.72	
No. 3 + 17.952		4.92			
不定形4				1.85	
不定形5				19.83	
合計				251.04	

3. 排 水 構 造 物 工

排水構造物工集計表

[illegible]

作業土工数量集計表										
工種	種別	細別	作業区分		床掘 小規模(m3)		埋戻 小規模(m3)		基面整正 (m2)	
			単位	数 量	単位数	数 量	単位数	数 量	単位数	数 量
排水構造物工	長尺U形側溝	300×300	m	88.86	/ 10		/ 10		5.90 / 10	52.43
	横断暗渠	400×250	m	8.82	1.04 / 10	0.92	/ 10		/ 10	
	集水桝	500×500 H=650	箇所	4.0	1.58 / 10	0.63	0.12 / 10	0.05	/ 10	
合計						1.55		0.05		52.43

長尺U形側溝

長尺U形側溝

位置

左右

数 量

一般部
300×300
(m)

摘 要

NO. 1+11. 256~NO. 2+6. 586

左

15.33

NO. 2+16. 832 $\sim$ NO. 3+18. 458

左

21. 63

N0. 3+19. 258~N0. 4+1. 532

左

3.00

NO. 1+11. 256 $\sim$ NO. 2+16. 032

右

24. 78

NO. 2+16.832~NO. 3+17.952

右

21. 12

NO. 3+18.765~NO. 4+0.889

右

3.00

合計

88. 86

4. 付 帯 工

構造物撤去工数量調書

仮排水管 (VU ϕ 200) 撤去

撤去工平面図より

$$L = 9.80 \qquad \qquad \qquad = \quad 9.80 \quad \text{m}$$


仮排水管 (VU ϕ 200) 処分

$$V = (0.216 \times 0.216 \times 3.14/4 - 0.20 \times 0.20 \times 3.14/4) \times 9.80 = 0.05 \text{ m3}$$

5. 単位数量計算書

長尺U形側溝 (A)

略 図



10 m 当り

T-25

Technical drawing of a concrete foundation (T-25) showing dimensions and material specifications.

Dimensions (mm):

- Overall width: 630
- Foundation width: 530
- Foundation height: 150
- Base layer height: 100
- Top layer height: 20
- Top layer width: 400
- Top layer height: 95
- Top layer width: 65

Materials:

- モルタル (1:3) (Mortar 1:3)
- 基礎コンクリート 18-8-25 (Foundation Concrete 18-8-25)
- 基礎砕石 (RC-40) (Foundation Gravel (RC-40))

[illegible]

10 基当り

Technical drawing of a drainage grate assembly, showing two views: a top view (plan) and a side view (elevation).

Top View (Plan):

- The overall dimensions are 800 mm by 800 mm.
- The central grate opening is 500 mm by 500 mm.
- The grate is labeled "グレーチング 蓋 (細目 斜付 ノスリ付)" (Grating Cover, Fine Mesh, Sloped, with Slits).
- The grate is specified as "T-14 (蓋 : 605 × 605 × 38) (受枠 : 625 × 625 × 44)".
- The grate is surrounded by a concrete frame (コンクリート) with a width of 150 mm on all sides.

Side View (Elevation):

- The overall height of the assembly is 650 mm.
- The grate is 50 mm thick.
- The concrete frame is 100 mm high.
- The base is labeled "基礎砕石 (再生切込砕石 RC-40)" (Base Gravel, Recycled Cut-in Gravel RC-40).
- The concrete frame is labeled "コンクリート (18-B-25)".
- The base gravel layer is 50 mm thick.
- The overall width of the assembly is 900 mm.

[illegible]

坂戸都市計画事業片柳土地区画整理事業
区画街路 6 - 7 2 号線外 2 路線
街 路 築 造 等 工 事

数 量 計 算 書
区6-73号線

令和 8 年 度

工事名：片柳土地地区画整理事業 区画街路6-72号線外2路線街路築造等工事

[illegible]

1. 道 路 土 工

掘削工

掘削工

測点

距離
(m)

横断面積
(m²)

平均横斷面積
(m²)

土量
(m³)

摘 要

No. 6 + 2.680

17.320

2.69

3.44

59. 58

No. 7

5.364

4. 19

4.25

22. 80

No.	7	+	5.364

2. 121

4.31

5.92

12.56

No.	7	+	7.485

7.52

合計

94. 94

埋戾



埋戾

合計

2. 鋪 装 工

車道舗装数量調書

車道舗装工	求積図より
No. 6+2.680～No. 7+7.485	
不定形＝三斜求積	＝13.34 m2



符号	底辺(下底)	高さ	上底	角度	倍面積
1	4.920	0.159	-	-	0.782
2	7.064	1.357	-	-	9.586
3	8.718	1.870	-	-	16.303
倍面積(m2)					26.671
面積(m2)					13.336

上層路盤（車道部）

[illegible]

3. 排 水 構 造 物 工

作業土工数量集計表										
工種	種別	細別	作業区分		床掘 小規模 (m3)		埋戻 小規模 (m3)		基面整正 (m2)	
			単位	数 量	単位数量	数 量	単位数量	数 量	単位数量	数 量
排水構造物工	長尺U形側溝	300×300	m	51.36	/ 10		/ 10		5.90 / 10	30.30
合計						0.00		0.00		30.30

長尺U形側溝

長尺U形側溝

位置

左右

数 量

一般部
300×300
(m)

摘 要

NO. 6+2. 7~NO. 7+7. 5

右

25. 58

NO. 6+2. 7 $\sim$ NO. 7+7. 5

左

25. 78

合計

51. 36

4. 単位数量計算書

10 m 当り

$300 \times 300 \times 4000$
歩車道用

Technical drawing of a curb and cover assembly for pedestrian use. The drawing shows a cross-section with dimensions: total width 540mm (70mm curb, 400mm cover, 70mm curb), total height 600mm (500mm curb, 100mm base). The curb is 100mm high and 300mm wide. The base is 100mm high and 540mm wide, composed of 120mm curb, 300mm base gravel, and 120mm curb. The cover is 300mm wide and 400mm long. The curb is made of SUS mesh and the base is RC-40 concrete.

Technical drawing of a curb and cover assembly for pedestrian use. The drawing shows a cross-section with dimensions: total width 540mm (70mm curb, 400mm cover, 70mm curb), total height 600mm (500mm curb, 100mm base). The curb is 100mm high and 300mm wide. The base is 100mm high and 540mm wide, composed of 120mm curb, 300mm base gravel, and 120mm curb. The cover is 300mm wide and 400mm long. The curb is made of SUS mesh and the base is RC-40 concrete.

[illegible]

坂戸都市計画事業片柳土地区画整理事業
区画街路 6 -72 号線外 2 路線
街路築造等工事

数量計算書
区6-4号線

令和 8 年 度

[illegible]

1. 道 路 土 工

土 工 集 計 表

[illegible]

土 工 数 量 調 書		
掘削		
V = 道路掘削		
= 46.14		= 46.14 m3
路肩盛土		
V = 路肩盛土		
= 3.42		= 3.42 m3
埋戻		
V = 道路埋戻		
= 3.42		= 3.42 m3
残土運搬処分		
V = 道路掘削(土砂)-(道路盛土+埋戻)/0.9		
= 46.14	- (3.42 + 3.42) / 0.9	= 38.54 m3

盛土工 (路肩盛土)

[illegible]

路床置換工(RC-40)


[illegible]

2. 鋪 装 工

車道舗装数量調書

車道舗装工 求積図より
No. 7+8. 779～No. 7+10. 176

不定形＝ 三斜求積 ＝ 6.88 m2



不定形2					
符号	底辺(下底)	高さ	上底	角度	倍面積
1	5.115	1.345	-	-	6.880
2	5.115	1.344	-	-	6.875
倍面積 (m2)					13.755
面積 (m2)					6.878

[illegible]

測点

距離
(m)幅員
(m)

平均幅員
(m)

面積
(m²)

摘 要

No. 7

	10.500

	4.92
--	------

	4.92

	51.66

道路幅6.0m—
U形側溝0.54m
—U形側溝0.54m

No.	7	+	5.300
-----	---	---	-------

	5.300

4.92

4.92

	26.08

No.	7	+	8.555
-----	---	---	-------

	3.255

4.92

	4.92

	16.01

No.	7	+	8.779
-----	---	---	-------

0.224

4.92

	4.92
--	------

	1. 10

合計

	94.85
--	-------

表層（車道部）

合計

3. 排 水 構 造 物 工

排水構造物工集計表

[illegible]

作業土工数量集計表										
工種	種別	細別	作業区分		床掘 小規模(m3)		埋戻 小規模(m3)		基面整正 (m2)	
			単位	数 量	単位数量	数 量	単位数量	数 量	単位数量	数 量
排水構造物工	長尺U形側溝	300×300	m	38.28	/ 10		/ 10		5.90 / 10	22.59
合計						0.00		0.00		22.59

長尺U形側溝

長尺U形側溝

位置

左右

数 量

歩車道用
300×300
(m)

摘 要

NO. 6+9. 500~NO. 7+8. 555

左

19. 05

N0. 6+9. 500~N0. 7+8. 779

右

19. 23

合計


38. 28

4. 付 帯 工

[illegible]

5. 単位数計算書

長尺U形側溝(A)

略 図

管きよ工

6-72号線

管きょ工数量集計表

工 種	種 別	細 別	規 格	単位	数 量	備 考
汚水排水工	路線延長			m	48.24	
		管渠延長		m	47.34	
	基礎延長		砂基礎	m	47.20	
		管路土工	機械掘削	BH0.20m3	m3	65.11
		埋戻	BH0.20m3 再生砂	m3	59.23	
		残土等処分		m3	65.11	
		管基礎工	砂基礎	m3	4.01	
	マンホール工	組立マンホール設置	1号 人孔深2.0m以下	箇所	1	
		底部工	1号	箇所	1	
		蓋及び口環	T-14	組	1	
		底版	有効高130	個	1	
		管取付壁	900×1200	個	1	
		斜壁ブロック	600×900×300	個	1	
		調整リング	100mm	個	2	
		調整金具	25mm	個	1	
		可とう継手	VUφ200	個	2	
		削孔	管種Vuφ200	箇所	1	
		下水キャップ	設置 Vuφ200	個	1	

VU200土工調書(1)

路線番号	マンホール	舗装区分	路線延長	マンホール		地盤高	管底高	舗装厚		掘削深		掘削		
	番号			区分	壁厚	計画	計画	現況	計画	計画	幅	土砂	路盤	
	上流側			上流側 D1	t1	上流側	上流側	舗装	舗装+路盤	上流側	平均			上端B1
	下流側			下流側 D2	t2	下流側	下流側	h1	h1'	下流側	H			下端B2
				cm	m	cm	mm	m	m	m	m	m	m	m ³
112-2	管止め					22.03	20.589			0.95		0.82		
	113-1		20.24	1号	90	75	22.02	20.528			1.00	0.98	0.82	16.26
113-1	113-1			1号	90	75	22.02	20.372			1.16		2.04	
	管止め		28.00				22.06	20.302			1.27	1.22	0.82	48.85
												</		

VU200土工調書(2)

路線番号	基礎延長 L2 m	基礎 90° 砂基礎		埋戻(再生砂)			備考
		単位 土量 m³/m	土量 m³	埋戻 単位 土量 m³/m	管回り m³	管上部 V3 m³	
112-2	19.72	0.082	1.62	0.222	4.49	9.36	
113-1	27.48	0.087	2.39	0.304	8.51	36.87	
計	47.20		4.01		13.00	46.23	
						59.23	

L2=L1-D1/2-t1-D2/2-t2

基礎単位数量=B×0.100

管回り単位数量=(0.316×(B1+B2)/2-0.216^2×π/4)

V3=(H-0.416)×L1×(B1+B2+.416)/2

VU200管路調書



路線番号	マンホール 番号	路線延長	マンホール 区分		控除長	管路延長	継手 (0.075m/本)	直管		備考
	上流側		上流側				上流側			
	下流側		下流側				下流側			
			m	cm			m			
112-2	管止め	20.24				19.79		19.72		
	113-1		1号	90	0.45		1			
113-1	113-1	28.00	1号	90	0.45	27.55	1	27.48		
	管止め									

組立人孔(円形90) (1)

番号	人孔深	地盤高	流入管		流出管		落差	副管	底版	管取付壁					
	m	m	径	管底高	径	管底高			130	600	900	1200	1500	1800	
No.113-1	1.648	22.02	200	20.528	200	20.372			1				1		

組立人孔(円形90) 組立人孔(円形90) (2)

番号	人孔深	地盤高	直壁						斜壁 600×900			ブロック計	蓋・受枠 t=11cm		調整高	調整金具		調整リング		上部調整高
	m	m	300	600	900	1200	1500	1800	300	450	600	m	T14	T25	m	25	45	100	150	mm
No.113-1	1.648	22.02							1			1.50	1		0.208	1		2		8
計			0	0	0	0	0	0	1	0	0		1	0		1	0	2	0	

 				
名称	規格	算式	単位	数量
インバート コンクリート工		$0.90^2 \times \pi / 4 \times 0.27 - 0.20^2 \times \pi / 4 \times 0.90 \div 2$	m3	0.16
インバート モルタル上塗り		$0.90^2 \times \pi / 4 - 0.20 \times 0.9 + 0.20 \times \pi \div 2 \times 0.9$	m2	0.74
		—1号組立マンホール 1箇所当り—		
再生砕石	RC-40	$1.10^2 \times \pi / 4 \times 0.20$	m3	0.19

管きょ工

6-73号線

管きょ工数量集計表

工 種	種 別	細 別	規 格	単位	数 量	備 考
汚水排水工	路線延長			m	28.00	
	管渠延長			m	27.55	
	基礎延長		砂基礎	m	27.48	
	管路土工	機械掘削	BH0.20m3	m3	17.91	
		埋戻	BH0.20m3 再生砂	m3	14.58	
		残土等処分		m3	17.91	
	管基礎工		砂基礎	m3	2.25	
	マンホール工	可とう継手	VU φ 200	個	1	
		削孔	管種Vu φ 200	箇所	1	

VU200土工調書(1)

路線番号	マンホール	舗装区分	路線延長	マンホール			地盤高	管底高	舗装厚		掘削深		掘削		
	番号			区分	壁厚	計画	計画	現況	計画	計画	幅	土砂	路盤		
	上流側			上流側 D1	t1	上流側	上流側	舗装	舗装・路盤	上流側	平均			上端B1	
	下流側			下流側 D2	t2	下流側	下流側	h1	h1'	下流側	H			下端B2	
				cm	m	cm	mm	m	m	m	m	m	m	m ³	m ³
111-3	113-1			1号	90	75	22.02	20.795			0.73		0.82		
	管止め		28.00				22.01	20.703			0.82	0.78	0.82	17.91	

VU200土工調書(2)

路線番号	基礎延長 L2 m	基礎 90° 砂基礎		埋戻(再生砂)			備考
		単位 土量 m ³ /m	土量 m ³	埋戻 単位 土量 m ³ /m	管回り m ³	管上部 V3 m ³	
111-3	27.48	0.082	2.25	0.222	6.22	8.36	
計	27.48		2.25		6.22	8.36	
						14.58	

$L2 = L1 - D1/2 - t1 - D2/2 - t2$
基礎単位数量 $= B \times 0.100$
管回り単位数量 $= (0.316 \times (B1 + B2) / 2 - 0.216^2 \times \pi / 4)$
 $V3 = (H - 0.416) \times L1 \times 0.82$

VU200管路調書

路線番号	マンホール 番号	路線延長	マンホール 区分		控除長	管路延長	継手 (0.075m/本)	直管		備考
	上流側		上流側				上流側			
	下流側		下流側				下流側			
			m	cm			m			
111-3	113-1	28.00	1号	90	0.450	27.55	1	27.48		
	管止め									
				</						

管きよ工

6-4号線

管きょ工数量集計表

工 種	種 別	細 別	規 格	単位	数 量	備 考
汚水排水工	路線延長			m	20.00	
	管渠延長			m	20.00	
	基礎延長		砂基礎	m	20.00	
	管路土工	機械掘削	BH0.20m3	m3	14.43	
		埋戻	BH0.20m3 再生砂	m3	12.05	
		残土等処分		m3	14.43	
	管基礎工		砂基礎	m3	1.64	
	下水キャップ		設置Vuφ200	個	1	

VU200土工調書(1)

路線番号	マンホール	舗装区分	路線延長	マンホール		地盤高	管底高	舗装厚		掘削深		掘削		
	番号			区分	壁厚	計画	計画	現況	計画	計画		幅	土砂	路盤
	上流側			上流側 D1	t1	上流側	上流側	舗装	舗装・路盤	上流側	平均	上端B1		
	下流側			下流側 D2	t2	下流側	下流側	h1	h1'	下流側	H	下端B2		
		cm	m	cm	mm	m	m	m	m	m	m	m	m ³	m ³
224-1	管止め					19.77	18.349			0.93		0.82		
	管止め		20.00			19.59	18.277			0.82	0.88	0.82	14.43	
計			20.00										14.43	
												残土処分(土砂)		
												14.43		
												H=地盤高-管底高-h1+0.108 V1=L1×H×(B1+B2)/2 V2=L1×h1×B1		

VU200土工調書(2)

路線番号	基礎延長 L2 m	基礎		埋戻(再生砂)			備考
		90° 砂基礎		埋戻	管回り	管上部	
		単位 土量	土量	単位 土量			
		m ³ /m	m ³	m ³ /m			
224-1	20.00	0.082	1.64	0.222	4.44	7.61	
計	20.00		1.64		4.44	7.61	
						12.05	
	L2=L1-D1/2-t1-D2/2-t2 基礎単位数量=B×0.100 管回り単位数量=(0.316×(B1+B2)/2-0.216^2×π/4) V3=(H-0.416)×L1×0.82						

VU200管路調書

路線番号	マンホール 番号	路線延長	マンホール 区分	控除長	管路延長	継手 (0.075m/本)	直管		備考
	上流側		上流側			上流側			
	下流側		下流側			下流側			
			m	cm		m			
224-1	管止め	20.00			20.000		20.000		
	管止め								