

数 量 総 括 表

工事区分 (LEVEL1)	工 種 (LEVEL2)	種 別 (LEVEL3)	細 別 (LEVEL4)	規 格 (LEVEL5)	単位	数値	設計数量	積算数量	日数・ 人数等	摘 要
	道路修繕									
	舗装工									
	新河原井橋(下り線)	橋面舗装工	路面切削	平均切削厚 t=5cm	m ²	1	578.6	579		夜間
			切削As殻運搬処理		m ³	1	28.9	29		夜間
			舗装版破碎	平均厚 t=3cm	m ²	1	578.6	579		夜間
			破碎As殻運搬処理	シート混じり	m ³	1	17.4	17		夜間
			橋面防水工	塗膜系防水	m ²	1	578.6	579		夜間
			導水テープ		m	1	53.2	53		夜間
			基層	改質Ⅲ型WF As t=4cm	m ²	1	578.6	579		夜間
			表層	改質Ⅲ型As t=4cm	m ²	1	578.6	579		夜間
		区画線工	熔融式区画線	実線・白・15cm	m	10	210.4	210		夜間
			熔融式区画線	破線・白・15cm	m	1	18.0	18		夜間
			熔融式区画線	矢印・白・15cm換算	m	1	7.9	8		夜間
		舗装工								
		(取付道路)	路面切削	平均切削厚 t=10cm	m ²	1	769.6	770		夜間
			切削As殻運搬処理		m ³	1	77.0	77		夜間
			基層	改質Ⅱ型As t=5cm	m ²	1	458.1	458		夜間
			基層	改質Ⅲ型As t=5cm	m ²	1	311.5	312		夜間
			表層	改質Ⅲ型As t=5cm	m ²	1	769.6	770		夜間

		区画線工	溶融式区画線	実線・白・15cm	m	10	381.8	380		夜間
			溶融式区画線	破線・白・15cm	m	1	30.0	30		夜間
			溶融式区画線	実線・白・45cm	m	1	3.0	3		夜間
			溶融式区画線	矢印・白・15cm換算	m	1	14.6	15		夜間
	舗装工									
	小林橋	橋面舗装工	路面切削	平均切削厚 t=6cm	m ³	1	224.3	224		夜間
			切削As殻運搬処理		m ³	1	13.5	14		夜間
			橋面防水工	塗膜系防水	m ²	1	224.3	224		夜間
			導水テープ		m	1	15.0	15		夜間
			表層	改質Ⅲ型As t=6cm	m ²	1	224.3	224		夜間
		区画線工	溶融式区画線	実線・白・15cm	m	1	59.8	60		夜間
			溶融式区画線	実線・黄・15cm	m	1	29.9	30		夜間
	交通誘導警備員									
	交通誘導警備員	交通誘導警備員	交通誘導警備員A	夜間	式	1	1	1		夜間
			交通誘導警備員B	夜間	式	1	1	1		夜間
	間接工事費									
	共通仮設費(積分)	運搬費	建設機械運搬費	切削機	式	1	1	1		損料なし 昼間
			建設機械運搬費	切削機	式	1	1	1		損料あり 昼間

数 量 計 算 書 （新河原井橋（下り線））					
種別／細別	規格・寸法	数 式	数 量	単位	摘 要
橋面舗装工					
路面切削	平均切削厚 t=5cm	52.6m×（7.25m+3.75m）	578.6	m ²	
切削As殻運搬処理		路面切削578.60m ² ×0.05m	28.9	m ³	
舗装版破碎	平均厚 t=3cm	路面切削と同じ	578.6	m ²	
破碎As殻運搬処理	シート混じり	舗装版破碎578.60m ² ×0.03m	17.4	m ³	
橋面防水工	塗膜系防水	路面切削と同じ	578.6	m ²	
	（導水パイプ）	52.6+41.1+52.4+10.5+19.6+10.9	187.1	m	
		187.1m/578.6m ² ×100	32.34	m/100m ²	
	（目地材）	187.1+53.2	240.3	m	
		240.3m/578.6m ² ×100	41.53	m/100m ²	
導水テープ		7.0+5.9+5.0+5.2+9.8+10.3+3.6+6.4	53.2	m	
基層	改質Ⅲ型WF As t=4cm	路面切削と同じ	578.6	m ²	
表層	改質Ⅲ型As t=4cm	路面切削と同じ	578.6	m ²	
区画線工					
溶融式区画線	実線・白・15cm	52.6m × 4本	210.4	m	外側線
溶融式区画線	破線・白・15cm	6.0m × 3本	18.0	m	中央線
溶融式区画線	矢印・白・15cm換算	7.9m × 1本	7.9	m	右折

数 量 計 算 書 (取付道路)					
種別／細別	規格・寸法	数 式	数 量	単位	摘 要
舗装工					
		面積計算書より			
路面切削	平均切削厚 t=10cm	$458.1\text{m}^2 + 311.5\text{m}^2$	769.6	m^2	
切削As殻運搬処理		路面切削 $769.60\text{m}^2 \times 0.1\text{m}$	77.0	m^3	
		右折車線			
基層	改質Ⅱ型As t=5cm	458.1m^2	458.1	m^2	
		下り車線			
基層	改質Ⅲ型As t=5cm	311.5m^2	311.5	m^2	
表層	改質Ⅲ型As t=5cm	路面切削と同じ	769.6	m^2	
区画線工					
		$116.6 + 89.6 + 41.4 + 38.4$			
溶融式区画線	実線・白・15cm	$+ 51.2 + 44.6$	381.8	m	外側線
溶融式区画線	破線・白・15cm	$6.0\text{m} \times 5\text{本}$	30.0	m	中央線
溶融式区画線	実線・白・45cm	3.0m	3.0	m	停止線
溶融式区画線	矢印・白・15cm換算	$6.66\text{m} + 7.9\text{m}$	14.6	m	右折

舖 裝 面 積 計 算 書

右折車線

測點 No.	點 (m)	距 離 (m)	路面切削、基層、表層			摘 要
			幅 (m)	平 均 (m)	面 積 (m²)	
0			0.0			
1		20.000	2.1	1.05	21.0	
2		20.000	4.2	3.15	63.0	
2 + 9.200	9.200		4.5	4.35	40.0	
2 + 9.200	0.000		3.0	3.75	0.0	
3		10.800	3.0	3.00	32.4	
4		20.000	3.0	3.00	60.0	
5		20.000	3.0	3.00	60.0	
5 + 16.700	16.700		3.0	3.00	50.1	
6		3.300	0.0	1.50	5.0	
8 + 13.200			0.0	0.00	0.0	
8 + 16.200	3.000		3.0	1.50	4.5	
9		3.800	3.0	3.00	11.4	
10		20.000	3.0	3.00	60.0	
10 + 16.900	16.900		3.0	3.00	50.7	
合計		163.7			458.1	

舖 裝 面 積 計 算 書

下り車線

測 No.	點 (m)	距 離 (m)	路面切削、基層、表層			摘 要
			幅 (m)	平 均 (m)	面 積 (m²)	
8	+	5.700				
			0.0			
8	+	12.300	6.600	6.5	3.25	21.5
9		7.700	6.5	6.50	50.1	
10		20.000	6.5	6.50	130.0	
10	+	16.900	16.900	6.5	6.50	109.9
		</				

数 量 計 算 書 （小林橋）

種別／細別	規格・寸法	数 式	数 量	単位	摘 要
橋面舗装工					
路面切削	平均切削厚 t=6cm	29.9m×7.5m	224.3	m ²	
切削As殻運搬処理		路面切削224.25m ² ×0.06m	13.5	m ³	
橋面防水工	塗膜系防水	路面切削と同じ	224.3	m ²	
	(導水パイプ)	29.9m × 2	59.8	m	縦断方向
		59.8m/224.3m ² ×100	26.67	m/100m ²	
	(目地材)	29.9m × 2 + 7.5m × 2	74.8	m	
		74.8m/224.3m ² ×100	33.36	m/100m ²	
導水テープ		7.5m × 2	15.0	m	横断方向
表層	改質Ⅲ型As t=6cm	路面切削と同じ	224.3	m ²	
区画線工					
溶融式区画線	実線・白・15cm	29.9m × 2本	59.8	m	外側線
溶融式区画線	実線・黄・15cm	29.9m	29.9	m	中央線